

STATE OF UTAH  
DIVISION OF OIL, GAS AND MINING

APPLICATION FOR PERMIT TO DRILL OR DEEPEN

5. Lease Designation and Serial Number: <b>PRIVATE</b>	
6. If Indian, Allottee or Tribe Name: <b>N/A</b>	
7. Unit Agreement Name: <b>N/A</b>	
8. Farm or Lease Name: <b>HUBER-JENSEN</b>	
9. Well Number: <b>2 - 9</b>	
10. Field and Pool, or Wildcat: <b>CASTLEGATE</b>	
11. Qtr/Qtr, Section, Township, Range, Meridian: <b>NENW 9-12S-10E</b>	
12. County: <b>CARBON</b>	
13. State: <b>UTAH</b>	
14. Distance in miles and direction from nearest town or post office: <b>10 AIR MILES NNE OF HELPER</b>	
15. Distance to nearest property or lease line (feet): <b>990'</b>	16. Number of acres in lease: <b>2,552.91</b>
17. Number of acres assigned to this well: <b>160</b>	18. Distance to nearest well, drilling, completed, or applied for, on this lease (feet): <b>2873'</b>
19. Proposed Depth: <b>5,600'</b>	20. Rotary or cable tools: <b>ROTARY</b>
21. Elevations (show whether OF, RT, GR, etc.): <b>7,240' UNGRADED</b>	22. Approximate date work will start: <b>SEPT. 15, 2000</b>

23. PROPOSED CASING AND CEMENTING PROGRAM

SIZE OF HOLE	GRADE, SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH	QUANTITY OF CEMENT
12-1/4"	8-5/8" K-55	24#	500'	365 sx Class G
7-7/8"	5-1/2" J-55	17#	5,600'	830 sx (DV @ 4,000')

DESCRIBE PROPOSED PROGRAM: If proposal is to deepen, give data on present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blowout preventer program, if any.

Request exception because of topography (location was picked to avoid an extensive wetland and to protect wildlife habitat as requested by DWR). Exception is to section line (330' instead of  $\geq 460'$ ), not to a well. Orthodox location would be in a wetland.

Orthodox well could be drilled at 460 FN & 1780 FE 9-12s-10e, but it would be in a wetland. Request permission to drill at 330' FNL & 1520' FWL 9-12s-10e. This is the only well in the quarter section. There are no producing wells within +5,000'. Wells (see Page 11) could be drilled in 8 offsetting units. Huber is owner of all drilling units and leases within minimum +4000' radius of proposed exception. This includes all 8 directly or diagonally offsetting drilling units.

24. Name & Signature: Brian Wood (505) 466-8120 Title: CONSULTANT Date: 8-5-00

(This space for State use only)

API Number Assigned: 43-007-30735

Approved by the  
Utah Division of  
Oil, Gas and Mining


RECEIVED

cc: Scott

Date: 01/08/01 / 180 09 2000


By: [Signature] DIVISION OF  
OIL, GAS AND MINING

Well Location Plat



Well Location Description

J.M. HUBER CORPORATION  
Huber - Jensen 2-9  
330' FNL & 1520' FWL  
Section 9, T.12 S., R.10 E., SLM  
Carbon County, UT  
7240' grd. el. ( from GPS )



12 July 2000

*Gerald G. Huddleston*

Gerald G. Huddleston, LS

The above is true and correct to my knowledge and belief.

HUDDLESTON LAND SURVEYING - BOX KK - CORTEZ, CO - (970) 565 -3330

J. M. Huber Corporation  
Huber-Jensen 2-9  
330' FNL & 1520' FWL  
Sec. 9, T. 12 S., R. 10 E.  
Carbon County, Utah

PAGE 1

### Drilling Program

<u>1. Formation Name</u>	<u>Depth from GL</u>	<u>Depth from KB</u>	<u>Subsea Depth</u>
Colton Fm	0'	12'	+7,240'
Flagstaff Ls	105'	117'	+7,135'
North Horn Fm	440'	452'	+6,800'
Price River Ss	3,740'	3,752'	+3,500'
Castle Gate Ss	4,240'	4,252'	+3,000'
Blackhawk Coal	4,540'	4,552'	+2,700'
Kenilworth Coal	5,240'	5,252'	+2,000'
Aberdeen Ss	5,440'	5,452'	+1,800'
Total Depth	5,600'	5,612'	+1,647'

(All depths are based on an ungraded ground level of 7,240')

### 2. NOTABLE ZONES

Blackhawk, Kenilworth, and Castlegate coals are the goals. No other oil or gas zones are expected. Flagstaff, North Horn, and coal zones are anticipated water zones.

### 3. PRESSURE CONTROL (Also see "5." on PAGE 2)

A  $\approx 10"$  x 2,000 psi double ram BOP with 2,000 psi choke manifold will be used from bottom of surface casing to TD. (A typical 2,000 psi BOP is on Page 3. Actual model will not be known until the bid is let.) BOP system will be tested to 70% of the minimum internal yield before drilling the surface casing shoe. System will be tested at least once every 30 days. Tests will be recorded in the driller's log. BOPs will be inspected and operated daily to assure good mechanical working order.

J. M. Huber Corporation  
Huber-Jensen 2-9  
330' FNL & 1520' FWL  
Sec. 9, T. 12 S., R. 10 E.  
Carbon County, Utah

PAGE 2

#### 4. CASING & CEMENTING

<u>Hole Size</u>	<u>O.D.</u>	<u>Weight</u>	<u>Grade</u>	<u>Type</u>	<u>Age</u>	<u>≈Setting Depth</u>
12-1/4"	8-5/8"	24	K-55	ST&C	New	500'
7-7/8"	5-1/2"	17	J-55	LT&C	New	5,600'

Surface casing will be circulated to surface with 365 sx Class G Premium + 2% CaCl<sub>2</sub> + Cello Flake. Weight = 15.6 ppg. Yield = 1.20 cu ft/sk. Excess = 100%

Long string will be cemented to surface with DV tool set at ≈4,000'. Actual volumes will be determined by caliper log.

First stage (≈4000' {=DV} to TD) of long string will be cemented with 305 sx Class G Premium + 1% Microbond + 0.3% CFR-3 + 3% Halad. Weight = 15.6 ppg. Yield = 1.20 cu ft/sk. Excess = 30%

Second stage lead (≈3950' {=50' above DV} to surface) of long string will be cemented with ≈475 sx Halliburton Lite w/ 65/35 poz mix + 2% CaCl<sub>2</sub>. Weight = 12.7 ppg. Yield = 1.87 cu ft/sk. Excess = 30%


Second stage tail (≈3950' {=50' above DV} to ≈4200' {200' below DV}) of long string will be cemented with 50 sx Class G Premium + 2% CaCl<sub>2</sub> + Flocele. Weight = 15.6 ppg. Yield = 1.19 cu ft/sk. Excess = 30%

#### 5. MUD PROGRAM


Fresh water gel (weight = 8.3 to 8.7 ppg, viscosity = 40-55, fluid loss = NC) will be used from surface to ≈500. Fresh water gel with caustic (weight = 8.7 to 9.1 ppg, viscosity = 38-45, fluid loss = 10-20 cc) may be used from surface casing shoe to TD. Will also drill with air.

## Pressure Control Equipment

2. Safety valves and necessary subs to fit all drill string in use will be available.



Minimum 2" Choke Line.  
Minimum 2" Kill Line.  
At Least One 2" Minimum Kill Line Valve.



**Note:** This equipment is designed to meet requirements for a 2-M rating standard per 43 CFR part 3160 (amended). Proper operation and testing of equipment will be carried out per standard. 2,000 psi equipment can be substituted in the drawing to meet minimum requirements per standard.

J. M. Huber Corporation  
Huber-Jensen 2-9  
330' FNL & 1520' FWL  
Sec. 9, T. 12 S., R. 10 E.  
Carbon County, Utah

PAGE 4

#### 6. DATA GATHERING

First deviation survey will be run  $\approx 250'$  below BSC. Additional surveys will be run every 500' to TD. Deviation limit will be  $1^\circ/100'$  and a maximum of  $5^\circ$  at TD. If deviation exceeds  $4^\circ$ , will decrease WOB, increase RPM, and survey at 250' intervals until corrected. If deviation becomes severe ( $>5^\circ$ ), may use a fourth stabilizer and convert to a full packed BHA.

Mud loggers will be on site from  $\approx 1,500'$  to TD. They will have full chromatograph. Will collect samples every 30' from  $\approx 1,500'$  to  $\approx 2,500'$ . Will collect samples every 10' from  $\approx 2,500'$  to TD.

Will run following log suites:

HRI/DSN/SDL/GR (EVR Mode): 4000' to TD  
HRI/DSN/SDL/GR: BSC TO TD

#### 7. DOWN HOLE CONDITIONS

Maximum anticipated bottom hole pressure is  $\approx 2,240$  psi. No hydrogen sulfide, abnormal pressures, nor abnormal temperatures are expected.

#### 8. MISCELLANEOUS

Projected spud date is September 15, 2000. It will take  $\approx 2$  weeks to drill the well and  $\approx 3$  weeks to complete the well.

Castlevue Hospital is a half hour drive away in Price on 590 East 100 North. Their phone number is (435) 637-4800.

## Surface Use Plan

### 1. EXISTING ROADS & DIRECTIONS (See PAGES 9 & 10)

From the junction of US 6 and US 191 north of Helper, Utah ...  
Go NE 7.8 miles on US 191 to the equivalent of Milepost 165.3  
Then turn left on the north side of a stock pen  
From the stock pen, go NW 2200' to the far side of a gravel pit  
Cross the berm and continue west 250' on a crowned and ditched road  
Then turn right and go NNW 1200' on a flagged route to a wash  
Bear left and go NW 500' on a flagged route to a ridge  
Then bear left and go WNW 550' on a flagged route to the 1-3 well site  
After exiting the N side of the 1-3 ....  
Go WSW 1000' to a fence  
Continue WSW 350' to a small hill  
Then bear right and go WNW 750' to the SE corner of the 1-4  
After exiting the south side of the 1-4 ...  
Go WSW 200' to the top of a hill  
Then bear left and go SW 2400' to the E side of the 2-9

### 2. ROAD TO BE BUILT OR UPGRADED (See PAGE 10)

The 2400' of new road from the 1-4 will be crowned and ditched with a 16' wide travel surface. If production results, then the new road will be graveled. Maximum disturbed width will not exceed 50'. Maximum grade is 7%. Maximum cut or fill will be 2'. At least 6 CMP culverts with these ~sizes will be installed as follows:

one 24" x 30': 750' W of the 1-4  
one 30" x 30': 850' W of the 1-4  
three 18" x 20': 1500' W of the 1-4  
one 18" x 20': on the E side of 2-9

3. EXISTING WELLS (See PAGE 10)

There are 2 gas wells and 1 P&A well within a mile radius. There are no existing oil, water, gas, injection, or disposal wells within a mile.

4. PROPOSED PRODUCTION FACILITIES (See PAGE 10)

A dehydrator-separator, meter run, and pump may be installed on the pad. All surface equipment will be painted a flat dark olive green color. Buried gas and water pipelines will be laid 2,400' east along the access road to the 1-4.

5. WATER SUPPLY

Water will be trucked from existing water well (right #91-4983) at Huber's central production facility in Section 11 or from town for the first 1500' of well bore. Produced water from Huber's wells will be used below 1500'.

6. CONSTRUCTION MATERIALS & METHODS

Topsoil and brush will be stripped and stockpiled north of the pad. Diversion ditch will be built north of the pad. Topsoil and brush along the new road will be windrowed beside the road. The reserve pit will be lined with minimum 12 mil plastic. A minimum 325' long silt fence will be installed south of the pad.

Gravel will be bought from the landowner or town.

7. WASTE DISPOSAL

The reserve pit will be fenced 4' high on 3 sides with 4 strands of barbed



J. M. Huber Corporation  
Huber-Jensen 2-9  
330' FNL & 1520' FWL  
Sec. 9, T. 12 S., R. 10 E.  
Carbon County, Utah

PAGE 7

wire or woven wire topped with barbed wire. The fourth side will be fenced once the rig moves off hole. The fence will be kept in good repair while the pit dries. No fluids will be discharged into the flare pit.

All trash will be placed in a trash cage. When full, it will be hauled to a state approved landfill. There will be no trash burning or disposal of trash in the reserve pit. Chemical toilets will be used for human waste. Their contents will be disposed of in state approved facilities.

No oil will be allowed on the reserve pit. Any oil which accumulates on the pit will be pumped or skimmed off and hauled to a state approved recycle facility. Once dry, the reserve pit contents will be buried in place. The pit will be backfilled sufficiently deep so that no liner is exposed.

Produced water will be piped to Huber's state approved lined  $\approx 9$  acre-foot evaporation pond at the Jensen 7-15 well.

#### 8. ANCILLARY FACILITIES

There will be no airstrip or formal camp. Camper trailers will be on site for the company man, roughnecks, mud logger, tool pusher, etc.

#### 9. WELL SITE LAYOUT

See PAGES 10 & 11 for depictions of the well pad, cross sections, cut and fill diagrams, reserve pit, burn pit, access road onto the pad, parking, living facilities, and rig orientation.

#### 10. RECLAMATION

After completing drilling, the well site and immediate area will be cleared of

J. M. Huber Corporation  
Huber-Jensen 2-9  
330' FNL & 1520' FWL  
Sec. 9, T. 12 S., R. 10 E.  
Carbon County, Utah

PAGE 8

all debris and material not needed for production.

Reclamation will start when the reserve pit is dry. At least 2' of cover will be placed on the reserve pit. All areas not needed for production will be backfilled, recontoured to match natural contours, and reserved topsoil and brush evenly spread. If the well is a producer, then enough topsoil will be kept aside to reclaim the rest of the pad. Disturbed areas will be ripped, harrowed, or scarified before seeding.

All reclaimed areas will be broadcast seeded in late fall or winter with seed mix specified by the surface owner. Owner's seed mix will include alfalfa, crested wheatgrass, Indian ricegrass, canby bluegrass, pubescent wheatgrass, Russian wild rye, slender wheatgrass, western wheatgrass, and yellow sweet clover. Seeded areas will be left rough and lightly harrowed or drug with a chain after seeding.

#### 11. SURFACE OWNER

The well site, road, and pipeline are all on private land owned by the Jensen family. Contact is Jerry Jensen @ (435) 637-6242 (office). Jerry is also the construction supervisor for Huber.

#### 12. OTHER INFORMATION

Closest hospital is a 25 minute drive south in Price. The Castlevew Hospital is at 300 North Hospital Drive. Phone number is (435) 637-4800.

#### 13. REPRESENTATION

Anyone having questions concerning the APD should contact:


J. M. Huber Corporation  
Huber-Jensen 2-9  
330' FNL & 1520' FWL  
Sec. 9, T. 12 S., R. 10 E.  
Carbon County, Utah


PAGE 9

Brian Wood  
Permits West, Inc.  
37 Verano Loop  
Santa Fe, NM 87505  
(505) 466-8120    FAX: (505) 466-9682    Mobile: (505) 699-2276

The field representative during drilling and production will be:


Larry Sessions  
J. M. Huber Corporation  
c/o Holiday Inn - Room 140  
838 Westwood Blvd., Price, Ut. 84501  
(435) 637-8880    FAX (435) 637-7707  
(temporary address & phones until office established)





J. M. Huber Corporation  
Huber-Jensen 2-9  
330' FNL & 1520' FWL  
Sec. 9, T. 12 S., R. 10 E.  
Carbon County, Utah

PAGE 12



Huber - Jensen # 2 - 9  
well pad




0' 50'  
Scale 1" = 50'

cut

1150 cy topsoil (0.5')  
1758 cy reserve pit  
2420 cy pad &  
above reserve pit  
1347 excess

fill

829 cy  
assumed 1:1 slopes  
20% shrink factor



WORKSHEET  
APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 08/09/2000

API NO. ASSIGNED: 43-007-30735

WELL NAME: HUBER-JENSEN 2-9

OPERATOR: J M HUBER CORPORATION ( N2380 )

CONTACT: BRIAN WOOD, AGENT

PHONE NUMBER: 505-466-8120

PROPOSED LOCATION:

NENW 09 120S 100E

SURFACE: 0330 FNL 1520 FWL

BOTTOM: 0330 FNL 1520 FWL

CARBON

CASTLEGATE ( 13 )

LEASE TYPE: 4-Fee

LEASE NUMBER: FEE

SURFACE OWNER: 4-Fee

PROPOSED FORMATION: BLKHK

INSPECT LOCATN BY: / /

Tech Review	Initials	Date
Engineering	<i>RSM</i>	8-21-00
Geology		
Surface		

RECEIVED AND/OR REVIEWED:

☒ Plat  
☒ Bond: Fed[] Ind[] Sta[] Fee[4]  
(No. 929103265 )  
☒ Potash (Y/N)  
☒ Oil Shale (Y/N) \*190 - 5 (B)  
☒ Water Permit  
(No. 91-4983 )  
☒ RDCC Review (Y/N)  
(Date: \_\_\_\_\_ )  
☒ Fee Surf Agreement (Y/N) *#Rec'd 1-3-2001*

LOCATION AND SITING:

\_\_\_ R649-2-3. Unit \_\_\_\_\_  
\_\_\_ R649-3-2. General  
\_\_\_ Siting: \_\_\_\_\_  
☒ R649-3-3. Exception  
\_\_\_ Drilling Unit  
Board Cause No: \_\_\_\_\_  
Eff Date: \_\_\_\_\_  
Siting: \_\_\_\_\_  
\_\_\_ R649-3-11. Directional Drill

COMMENTS:

Need Presite. (Conducted 8-17-2000)

STIPULATIONS:

① STATEMENT OF BASIS





**ENERGY**

A FAMILY OF SOLUTIONS

**J.M. Huber Corporation**

December 27, 2000

1050-17<sup>th</sup> Street  
Suite 1850  
Denver, CO 80265  
phone: (303) 825-7900  
fax: (303) 825-8300  
e-mail: dv\_cptrs@huber.co  
www.huber.com

Ms. Lisha Cordova  
Utah Division of Oil, Gas and Mining  
1594 West North Temple, Suite 1210  
Salt Lake City, Utah 84114-5801

Dear Lisha:

Enclosed is the original signed affidavit of completion of surface use agreement between J. M. Huber Corporation and James T. Jensen, Jerry Jensen and Dix Jensen for the Huber-Jensen 2-9 well located in Carbon County, Utah.

Thank you for your assistance in this matter. If you have any questions, please call me at (303) 825-7900.

Sincerely,

T. Reed Scott  
Consulting Engineer

Attachment

RECEIVED

DEC 29 2000

DIVISION OF  
OIL, GAS AND MINING



**ENERGY**

A FAMILY OF SOLUTIONS

**J.M. Huber Corporation**

1050-17<sup>th</sup> Street  
Suite 1850  
Denver, CO 80265  
phone: (303) 825-7900  
fax: (303) 825-8300  
e-mail: dvjsz@huber.com  
www.huber.com

December 27, 2000

**Affidavit of Completion of Surface Use Agreement**

On August 21, 2000 a written surface use agreement was entered into between J. M. Huber Corporation and James T. Jensen, Jerry Jensen and Dix Jensen for the use of land connected with the Huber-Jensen 2-9 well in Carbon County, Utah.

We will abide by the conditions as stated in the Surface Use Agreement.

On behalf of J. M. Huber Corporation:

A. J. Lydyard  
Vice President - Coalbed Methane Business Unit

Date: 12/27/00

State of Colorado)

ss

County of Denver)

Subscribed and sworn to before me this 27th day of December 2000 by A. J. Lydyard.

Witness my hand and notarial seal.

My commission expires: 4-2-02

  
Notary Public

RECEIVED

DEC 29 2000

DIVISION OF  
OIL, GAS AND MINING



State of Utah  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

Michael O. Leavitt  
Governor  
Kathleen Clarke  
Executive Director  
Lowell P. Braxton  
Division Director

1594 West North Temple, Suite 1210  
PO Box 145801  
Salt Lake City, Utah 84114-5801  
801-538-5340  
801-359-3940 (Fax)  
801-538-7223 (TDD)

January 8, 2001

J. M. Huber Corporation  
1050 Seventeenth St, Suite 1850  
Denver, CO 80265

Re: Huber-Jensen 2-9 Well, 330' FNL, 1520' FWL, NE NW, Sec. 9, T. 12 South, R. 10 East,  
Carbon County, Utah


Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann. § 40-6-1 *et seq.*, Utah Administrative Code R649-3-1 *et seq.*, and the attached Conditions of Approval, approval to drill the referenced well is granted.

Appropriate information has been submitted to DOGM and administrative approval of the requested exception location is hereby granted.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-007-30735.

Sincerely,



John R. Baza  
Associate Director

er

Enclosures

cc: Carbon County Assessor

**Operator:** J. M. Huber Corporation  
**Well Name & Number** Huber-Jensen 2-9  
**API Number:** 43-007-30735  
**Lease:** FEE

**Location:** NE NW      **Sec.** 9      **T.** 12 South      **R.** 10 East

### **Conditions of Approval**

**1. General**

Compliance with the requirements of Utah Admin. R. 649-1 *et seq.*, the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

**2. Notification Requirements**

The operator is required to notify the Division of Oil, Gas and Mining of the following actions during drilling of this well:

- 24 hours prior to cementing or testing casing
- 24 hours prior to testing blowout prevention equipment
- 24 hours prior to spudding the well
- within 24 hours of any emergency changes made to the approved drilling program
- prior to commencing operations to plug and abandon the well

The following are Division of Oil, Gas and Mining contacts and their work telephone numbers (please leave a voice mail message if the person is not available to take the call):

- Dan Jarvis at (801) 538-5338
- Carol Daniels at (801) 538-5284 (spud)

**3. Reporting Requirements**

All required reports, forms and submittals will be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.

**4. Compliance with the Conditions of Approval/Application for Permit to Drill outlined in the Statement of Basis. (Copy Attached)**

DIVISION OF OIL, GAS AND MINING

SPUDDING INFORMATION

Name of Company: J M HUBER CORPORATION

Well Name: HUBER-JENSEN 2-9

Api No.. 43-007-30735 LEASE TYPE: FEE

Section 09 Township 12S Range 10E County CARBON

Drilling Contractor BILL JR RATHOLE RIG #

SPUDDED:

Date 07//27/2001

Time

How DRY

Drilling will commence


Reported by JOE DUNKIN

Telephone # 1-435-823-4200

Date 08/01/2001 Signed: CHD

PLOT OF AN AREA WITH A RADIUS OF 5280 FEET  
S 330 FEET, E 1520 FEET OF THE NW CORNER,  
SECTION 9 TOWNSHIP 12S RANGE 10E SL BASE

N O R T H



UTAH DIVISION OF WATER RIGHTS  
NWPLAT      POINT OF DIVERSION LOCATION PRO

MAP CHAR	WATER RIGHT	CFS	QUANTITY AND/OR	AC-FT	SOURCE DESCRIPTION or WELL INFO DIAMETER      DEPTH      YEAR LOG	POIN NORTH
0	91 1335	.0000		.00	Unnamed Stream	
	WATER USE(S): Moynier, Lea      284 North Carbon Ave.					
1	91 1340	.0110		.00	Unnamed Spring	
	WATER USE(S): Moynier, Lea      284 North Carbon Ave.					
2	91 1354	.0000		.00	Unnamed Stream	
	WATER USE(S): Moynier, Lea      284 North Carbon Ave.					
3	91 4823	10.0000		.00	Underground Wells	N 750
	WATER USE(S): MUNICIPAL Price River Water Improvement District      P.O. Box 903					
4	91 4823	10.0000		.00	Underground Wells	N 750
	WATER USE(S): MUNICIPAL Price River Water Improvement District      P.O. Box 903					
5	91 1353	.0000		.00	Unnamed Stream	
	WATER USE(S): Moynier, Lea      284 North Carbon Ave.					
6	91 4823	10.0000		.00	Underground Wells	N 650
	WATER USE(S): MUNICIPAL Price River Water Improvement District      P.O. Box 903					
7	91 4823	10.0000		.00	Underground Wells	N 650
	WATER USE(S): MUNICIPAL Price River Water Improvement District      P.O. Box 903					
8	91 1338	.0000		.00	Unnamed Wash	
	WATER USE(S): Moynier, Lea      284 North Carbon Ave.					
9	91 280	.0000		2.20	Willow Creek	N 200
	WATER USE(S): MUNICIPAL OTHER Price River Water Improvement District      P.O. Box 903					
A	91 4823	10.0000		.00	Underground Wells	S 415
	WATER USE(S): MUNICIPAL Price River Water Improvement District      P.O. Box 903					
B	91 1337	.0110		.00	Spring Area	
	WATER USE(S): Moynier, Lea      284 North Carbon Ave.					
C	91 1336	.0110		.00	Unnamed Spring	

WATER USE(S):  
Moynier, Lea

284 North Carbon Ave.

D	<u>91 2387</u>	.0110	.00	Spring Area	
	WATER USE(S): USA Bureau of Land Management (Price Fie 125 South 600 West				
D	<u>91 4750</u>	.0000	.00	Unnamed Tributary to Willow Cr	
	WATER USE(S): STOCKWATERING OTHER USA Bureau of Land Management (Price Fie 125 South 600 West				
E	<u>91 4586</u>	.0000	.00	Unnamed Trib. to Willow Creek	
	WATER USE(S): STOCKWATERING OTHER USA Bureau of Land Management (Price Fie 125 South 600 West				
F	<u>91 1261</u>	.0110	.00	Unnamed Spring	
	WATER USE(S): Moynier, Pierre (Jr.) 748 North 400 East				
G	<u>91 4823</u>	10.0000	.00	Underground Wells	S 2000
	WATER USE(S): MUNICIPAL Price River Water Improvement District P.O. Box 903				
G	<u>91 4830</u>	2.0000	.00	6 3800 - 5000	S 2019
	WATER USE(S): IRRIGATION STOCKWATERING MUNICIPAL POWER OTHER PG&E Resources Company 6688 No. Central Expressway				
G	<u>91 4983</u>	.1600	.00	5 4878	S 2019
	WATER USE(S): IRRIGATION OTHER Anadarko Petroleum Corporation 9400 North Broadway				
H	<u>91 4823</u>	10.0000	.00	Underground Wells	S 2000
	WATER USE(S): MUNICIPAL Price River Water Improvement District P.O. Box 903				
I	<u>91 4830</u>	2.0000	.00	6 3800 - 5000	S 2065
	WATER USE(S): IRRIGATION STOCKWATERING MUNICIPAL POWER OTHER PG&E Resources Company 6688 No. Central Expressway				
I	<u>91 4983</u>	.1600	.00	5 4829	S 2065
	WATER USE(S): IRRIGATION OTHER Anadarko Petroleum Corporation 9400 North Broadway				
J	<u>91 4823</u>	10.0000	.00	Underground Wells	N 2100
	WATER USE(S): MUNICIPAL Price River Water Improvement District P.O. Box 903				
K	<u>91 4830</u>	2.0000	.00	6 3800 - 5000	N 2024
	WATER USE(S): IRRIGATION STOCKWATERING MUNICIPAL POWER OTHER PG&E Resources Company 6688 No. Central Expressway				
L	<u>91 4830</u>	2.0000	.00	6 3800 - 5000	N 1198
	WATER USE(S): IRRIGATION STOCKWATERING MUNICIPAL POWER OTHER PG&E Resources Company 6688 No. Central Expressway				
L	<u>91 4983</u>	.1600	.00	5 4617	N 1198
	WATER USE(S): IRRIGATION OTHER Anadarko Petroleum Corporation 9400 North Broadway				
M	<u>91 4830</u>	2.0000	.00	6 3800 - 5000	N 675
	WATER USE(S): IRRIGATION STOCKWATERING MUNICIPAL POWER OTHER PG&E Resources Company 6688 No. Central Expressway				
N	<u>91 1262</u>	.0110	.00	Unnamed Spring	
	WATER USE(S):				



Moynier, Pierre (Jr.)

748 North 400 East

O 91 4823 10.0000


.00 Underground Wells

N 650


WATER USE(S): MUNICIPAL

Price River Water Improvement District P.O. Box 903

---



COUNTY: CARBON SPACING: R649-3-2 (SEC 8)  
R649-3-3 (SEC 9) & CAUSE 220-2 (SEC 15)



Well name:		<b>8-00 JM Huber HJ 2-9</b>	
Operator:	<b>JM Huber Corp.</b>	Project ID:	<b>43-007-30735</b>
String type:	<b>Production</b>		
Location:	<b>Carbon Co.</b>		

**Design parameters:**

**Collapse**

Mud weight: 8.700 ppg  
Design is based on evacuated pipe.

**Minimum design factors:**

**Collapse:**

Design factor 1.125

**Burst:**

Design factor 1.00

**Environment:**

H2S considered? No  
Surface temperature: 75 °F  
Bottom hole temperature: 153 °F  
Temperature gradient: 1.40 °F/100ft  
Minimum section length: 368 ft

Cement top: 938 ft

**Burst**

Max anticipated surface pressure: 0 psi  
Internal gradient: 0.452 psi/ft  
Calculated BHP 2,531 psi

No backup mud specified.

**Tension:**

8 Round STC: 1.80 (J)  
8 Round LTC: 1.80 (J)  
Buttress: 1.60 (J)  
Premium: 1.50 (J)  
Body yield: 1.50 (B)

Non-directional string.

Tension is based on buoyed weight.  
Neutral point: 4,861 ft

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Internal Capacity (ft³)
1	5600	5.5	17.00	J-55	LT&C	5600	5600	4.767	193
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	2531	4910	1.94	2531	5320	2.10	83	247	2.99 J

Prepared RJK  
by: Utah Dept. of Natural Resources

Date: August 21, 2000  
Salt Lake City, Utah

**ENGINEERING STIPULATIONS: NONE**

Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.


Collapse is based on a vertical depth of 5600 ft, a mud weight of 8.7 ppg. The casing is considered to be evacuated for collapse purposes.

Burst strength is not adjusted for tension.

*Engineering responsibility for use of this design will be that of the purchaser.*

# 8-00 JM Huber HJ 2-9

## Casing Schematic



Well name:	<b>8-00 JM Huber HJ 2-8</b>	
Operator:	<b>JM Huber Corp.</b>	
String type:	Production	Project ID: 43-007-30734
Location:	Carbon Co.	

**Design parameters:**

**Collapse**

Mud weight: 8.700 ppg  
Design is based on evacuated pipe.

**Minimum design factors:**

**Collapse:**

Design factor 1.125

**Burst:**

Design factor 1.00

**Environment:**

H2S considered? No  
Surface temperature: 75 °F  
Bottom hole temperature: 153 °F  
Temperature gradient: 1.40 °F/100ft  
Minimum section length: 368 ft

Cement top: 938 ft

**Burst**

Max anticipated surface pressure: 0 psi  
Internal gradient: 0.452 psi/ft  
Calculated BHP 2,531 psi

No backup mud specified.

**Tension:**

8 Round STC: 1.80 (J)  
8 Round LTC: 1.80 (J)  
Buttress: 1.60 (J)  
Premium: 1.50 (J)  
Body yield: 1.50 (B)

Non-directional string.

Tension is based on buoyed weight.  
Neutral point: 4,861 ft

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Internal Capacity (ft³)
1	5600	5.5	17.00	J-55	LT&C	5600	5600	4.767	193
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	2531	4910	1.94	2531	5320	2.10	83	247	2.99 J

Prepared RJK  
by: Utah Dept. of Natural Resources

Date: August 21, 2000  
Salt Lake City, Utah

**ENGINEERING STIPULATIONS: NONE**

Collapse strength is based on the Westcott, Dunlop & Kernler method of biaxial correction for tension.

Collapse is based on a vertical depth of 5600 ft, a mud weight of 8.7 ppg. The casing is considered to be evacuated for collapse purposes.

Burst strength is not adjusted for tension.

*Engineering responsibility for use of this design will be that of the purchaser.*



# United States Department of the Interior

## BUREAU OF LAND MANAGEMENT

Utah State Office  
P.O. Box 45155  
Salt Lake City, UT 84145-0155

IN REPLY REFER TO  
UT-922

August 24, 2001

J.M. Huber Corporation  
Attn: Annette Hoover  
1050 17<sup>th</sup> Street, Suite 1050  
Denver, Colorado 80265

Gentlemen:

Enclosed is one approved copy of Communitization Agreement No. UTU79758. This agreement communitizes all rights as to natural gas and associated liquid hydrocarbons producible from the Blackhawk Coals Formation, covering the NW¼ of Section 9, Township 12 South, Range 10 East, SLB&M, Carbon County, Utah. This agreement conforms with the spacing set forth in Order No. 220-2 which was issued by the State of Utah, Board of Oil, Gas and Mining.

This agreement is effective as of July 3, 2001. The communitized area covers 160.00 acres and includes portions of Federal oil and gas lease UTU65948.

Approval of this agreement does not warrant or certify that the operator thereof and other holders of operating rights hold legal or equitable title to those rights in the subject leases which are committed hereto.

Minerals Management Service Form MMS-3160, "Monthly Report of Operations", must be submitted for this agreement beginning with the month in which drilling operations commence for ~~Well No. 2-9, NE¼ NW¼, Section 9, Township 12 South, Range 10 East, SLB&M, Carbon County, Utah, API # 43-007-30735~~, on a Patented Lease. Form MMS-3160 is to be mailed to the Minerals Management Service, Production Accounting Division, P. O. Box 17110, Denver, Colorado 80217.

Please furnish all interested principals with necessary evidence of this approval.

Sincerely,

/s/ Robert A. Henricks

Robert A. Henricks  
Chief, Branch of Fluid Minerals

**RECEIVED**

Enclosure

AUG 27 2001

DIVISION OF  
OIL, GAS AND MINING

bcc: Mineral Adjudication Group w/enclosure  
Field Manager - Moab w/enclosure  
Division Oil, Gas & Mining  
File - UTU79758  
MMS - Data Management Division (Attn: Rose Davalos)  
Agr. Sec. Chron.  
Fluid Chron.

UT922:TATHOMPSON:tt:8/24/01

# COMMUNITIZATION AGREEMENTS

TOWNSHIP 12 SOUTH

RANGE 10 EAST

6	5	4	3	2	1
7	8	<del>79758</del> <del>78951</del> 9	<del>78952</del> 10	11	12
18	17	16	<del>79750</del> 15	14	13
19	20	21	22	23	24
30	29	28	27	26	25
31	32	33	34	35	36



# DIVISION OF OIL, GAS AND MINING

## APPLICATION FOR PERMIT TO DRILL STATEMENT OF BASIS

Operator Name: J. M. Huber  
Name & Number: Huber-Jensen #2-9  
API Number: 43-007-30735  
Location: 1/4, 1/4 NE NW Sec. 9 T. 12 S R. 10 E County Carbon

### Geology/Ground Water:

The setting depth of the surface casing is 500 8 5/8 24#, cemented back to surface with 375 sx of premium class G cement. There are 28 points of diversion within 1 mile of this location, which were developed by several parties, with priority dates back to 1860, some of these are municipal and some are wells several of these may be completed in the Blackhawk coal the intended production zone in this well. A search made of the records at water rights showed that no water from active water wells is being produced from below 385', and that the proposed 500' of surface casing will cover these zones. The several springs and diversions along the gully east of the location may not active, but will be protected by the surface casing and the cement at the bottom of the long string. Produced water will be disposed of at an approved disposal facility.

Reviewer: K. Michael Hebertson Date: 17/Aug/2000

### Surface:

The surface owner was invited and attended the pre site for this location and made several changes to the proposed plan. Overall he was happy with the operators proposal. The surface owner was also made aware of the winter range and habitat concerns expressed by DWR, and the active Sage Grouse strutting area that has been identified by DWR. He was not sympathetic to their request and not interested in holding up work for the time frames requested. The surface owner requested that the cattle guard be reconstructed and a better gate installed with proper locks, he may also request some stipulation as to the winter drilling operations being proposed by Huber, as he is not in favor of drilling over the winter months.

Reviewer: K. Michael Hebertson Date: 28/Aug /2000

### Conditions of Approval/Application for Permit to Drill:

1. Location will be bermed around the top of the outside edge.
2. A pit liner of 12 MILS minimum thickness is required.
3. Top soil will be stored in a windrow on the North side of the reserve pit.
4. Water bars and turnouts will be place in sufficient numbers to keep the access road from becoming the preferred drainage course.

**ON-SITE PREDRILL EVALUATION**  
**Division of Oil, Gas and Mining**

OPERATOR: J.M. Huber Corporation

WELL NAME & NUMBER: Huber-Jensen #2-9

API NUMBER: 43-007-30735

LEASE: Fee FIELD/UNIT: Castlegate (013)

LOCATION: 1/4, 1/4 NE NW Sec: 9 TWP: 12S RNG: 10E 330 FNL 1520 FWL

LEGAL WELL SITING: 460 F SEC. LINE; 460 F 1/4, 1/4 LINE; 920 F ANOTHER WELL.

GPS COORD (UTM): X = 516,199 E; Y = 4,405,914 N

SURFACE OWNER: Jerry Jensen

**PARTICIPANTS**

Mike Hebertson (DOGM), Brian Wood (Permits West), Jerry Jensen, Larry Sessions (Anadarko)

**REGIONAL/LOCAL SETTING & TOPOGRAPHY**

This well is located on the second bench of the Wasatch Plateau about 3 miles south of the Roan Cliffs, in the area known as Emma Park. Mathis Canyon is to the southeast of the location about 2 miles. Willow Creek is a major active flowing stream to the east about 1 1/2 miles which flows to the south down Price Canyon. Other drainages intersect the major secondary and primary system flowing generally north and then east until they meet Willow Creek, thence to the Price River. The whole of Emma Park is open Sage Brush meadow with interspersed grass lands. The surface is of Tertiary & Cretaceous age rocks from the Flagstaff Limestone and the North Horn Conglomerate. The Flagstaff is of lacustrine origin and the North Horn is of a fluvial origin. There is no distinct contact between the two since the two have many complex overlapping facies in this area.

**SURFACE USE PLAN**

CURRENT SURFACE USE: Wildlife and livestock use.

PROPOSED SURFACE DISTURBANCE: A location 300 X 200, the access road will enter the pad on the north corner. 2,000' new will be required.

LOCATION OF EXISTING WELLS WITHIN A 1 MILE RADIUS: There is 1 P&A well and one producing well within one mile, all of which were drilled to the Mesa Verde and one new well completed to the Mesa Verde Black Hawk Coal.

LOCATION OF PRODUCTION FACILITIES AND PIPELINES: Will follow the roads and already established corridors in the abandoned field area. Pipelines and power lines will be installed from existing tie ins.

SOURCE OF CONSTRUCTION MATERIAL: Borrowed from the construction of the location. A commercial supplier will be used for the gravel pad or the material will be purchased from the landowner from a previous supply.

ANCILLARY FACILITIES: These are already in place.

**WASTE MANAGEMENT PLAN:**

Portable chemical toilets which will be emptied into the municipal waste treatment system; garbage cans on location will be emptied into centralized dumpsters which will be emptied into an approved landfill. No crude oil is expected to be produced. Drilling fluid, completion / frac fluid and cuttings will be buried in the pit after evaporation and slashing the pit liner. Used oil from drilling operations and

support is hauled to a used oil re-cycler and re-used. Produced water will be disposed of at an approved facility.

#### ENVIRONMENTAL PARAMETERS

AFFECTED FLOODPLAINS AND/OR WETLANDS: The floodplains and drainages will be protected with berms ditches and silt fences as necessary.

FLORA/FAUNA: Deer, Elk, Moose, Cougar, Eagles, Hawks, Other indigenous bird species, Aspen, varieties of grasses, Sage Brush, Rabbit Brush.

SOIL TYPE AND CHARACTERISTICS: Clay from the limestone which weathers to a dark tan to redish in color. Locally with sandstone inclusions and fossil trash or remains.

SURFACE FORMATION & CHARACTERISTICS: Flagstaff Limestone interbedded with the North Horn Formation which varies from a conglomerate to a thinly bedded sandstone and interfingers with the Flagstaff.

EROSION/SEDIMENTATION/STABILITY: No stability, or erosion problems with the selected site sedimentation will be mitigated with berms and diversions placed to contain runoff from the location and cut.

PALEONTOLOGICAL POTENTIAL: Not required.

#### RESERVE PIT

CHARACTERISTICS: The pit will be 125 X 50 X 10.

LINER REQUIREMENTS (Site Ranking Form attached): A synthetic liner will be required.

#### SURFACE RESTORATION/RECLAMATION PLAN

Will be signed and executed prior to issuance of the APD.

SURFACE AGREEMENT: Will be executed and affidavit will be sent to DOGM.

CULTURAL RESOURCES/ARCHAEOLOGY: Not required

#### OTHER OBSERVATIONS/COMMENTS

The access road will go around a pond at the exit from Highway 191. The new road will be placed on the south of the pond on higher ground than the existing two track and will also be the corridor for the utilities and pipelines. The tie in point for the pipeline already exists at the southeast corner of the 3-10 location. Several spacing issues were discussed including the exception spacing being applied for. A discussion of why the road could not come into the pad from the Matts Summit road revealed that the short way would entail crossing a marsh wetlands that the surface owner did not want disturbed.

#### ATTACHMENTS:

Photos were taken and will be placed on file.

K. Michael Hebertson  
DOGM REPRESENTATIVE

17/Aug/2000/ 10:15 M  
DATE/TIME

**Evaluation Ranking Criteria and Ranking Score  
For Reserve and Onsite Pit Liner Requirements**

<u>Site-Specific Factors</u>	<u>Ranking</u>	<u>Site Ranking</u>
Distance to Groundwater (feet)		
>200	0	
100 to 200	5	
75 to 100	10	
25 to 75	15	
<25 or recharge area	20	<u>10</u>
Distance to Surf. Water (feet)		
>1000	0	
300 to 1000	2	
200 to 300	10	
100 to 200	15	
< 100	20	<u>15</u>
Distance to Nearest Municipal Well (feet)		
>5280	0	
1320 to 5280	5	
500 to 1320	10	
<500	20	<u>0</u>
Distance to Other Wells (feet)		
>1320	0	
300 to 1320	10	
<300	20	<u>0</u>
Native Soil Type		
Low permeability	0	
Mod. permeability	10	
High permeability	20	<u>15</u>
Fluid Type		
Air/mist	0	
Fresh Water	5	
TDS >5000 and <10000	10	
TDS >10000 or Oil Base Mud Fluid	15	
containing significant levels of hazardous constituents	20	<u>5</u>
Drill Cuttings		
Normal Rock	0	
Salt or detrimental	10	<u>0</u>
Annual Precipitation (inches)		
<10	0	
10 to 20	5	
>20	10	<u>5</u>
Affected Populations		
<10	0	
10 to 30	6	
30 to 50	8	
>50	10	<u>0</u>
Presence of Nearby Utility Conduits		
Not Present	0	
Unknown	10	
Present	15	<u>10</u>
<b>Final Score</b>	<u>60</u>	(Level I Sensitivity)

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 6

**ENTITY ACTION FORM**

Operator: J. M. Huber Corporation

Operator Account Number: N 2380

Address: 1050 17th St. Suite #700

City Denver

State CO zip 80265

Phone Number: 303-825-7900

Well 1

API Number	Well Name	QQ	Sec	Twp	Rng	County
43-007-30735	Huber-Jensen 2-9	NENW	9	12S	10E	Carbon
Action Code	Current Entity Number	New Entity Number	Spud Date	Entity Assignment Effective Date		
A	99999	13317	July 29, 2001	10-1-01		
Comments:						

Well 2

API Number	Well Name	QQ	Sec	Twp	Rng	County
Action Code	Current Entity Number	New Entity Number	Spud Date	Entity Assignment Effective Date		
Comments:						

Well 3

API Number	Well Name	QQ	Sec	Twp	Rng	County
Action Code	Current Entity Number	New Entity Number	Spud Date	Entity Assignment Effective Date		
Comments:						

**ACTION CODES:**

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (Explain in 'comments' section)

Gary J. Johnson

Name (Please Print)

Signature

Consulting Petroleum Engineer

9/24/01

Title

Date

**RECEIVED**

OCT 5 1 2001

DIVISION OF  
OIL, GAS AND MINING



A FAMILY OF SOLUTIONS

RECEIVED

DEC 20 2001

DIVISION OF  
OIL, GAS AND MINING

**ENERGY**

**J.M. Huber Corporation**

1050 17<sup>th</sup> St., Ste. 700  
Denver, CO 80265

phone: (303) 825-7900  
fax: (303) 825-8300  
e-mail: dv\_cpjaw@huber.cc  
www.huber.com

December 20, 2001

Utah Division of Oil, Gas and Mining  
Carol Daniels  
1594 West North Temple, Suite 1210  
Box 145801  
Salt Lake City, UT 84114

RE: Form 8, Completion Report –  
Huber-Jensen 2-9, NENW Sec. 9, T12S, R10E, API # 43-007-30735  
Huber-Shimmin Trust 4-14, SWNW Sec. 14, T12S, R10E, API# 43-007-30662  
Huber-Jensen 1-8, NESE Sec. 8, T12S, R10E, API # 43-007-30768  
Huber-Jensen 1-4, SWSE Sec. 4, T12S, R10E, API # 43-007-30733

Dear Carol,

Enclosed you will find the Form 8's for the above-mentioned wells. We understand that the logging company will be forwarding copies of the logs to you for your well files. If you do not get them please let me know.

If you have any other questions or concerns please do not hesitate to call me at 303-825-7900.

Respectfully yours,

Judith A. Walter  
Regulatory Compliance – Contract Agent

Cc: J.M. Huber Field Office – Larry Sessions, 212 East 100 North, PO Box 551, Price, UT 84501  
Patina Oil & Gas Corp., 1625 Broadway, Suite 2000, Denver, CO 80202  
Correspondence  
Well File – 3 (Tom Erwin, Gary Johnson, WF)

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

AMENDED REPORT ☐ FORM 8  
(highlight changes)

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

1a. TYPE OF WELL: OIL WELL ☐ GAS WELL ☒ DRY ☐ OTHER \_\_\_\_\_  
b. TYPE OF WORK  
NEW ☒ HORIZ. ☐ DEEP. ☐ RE- ☐ DIFF. ☐

2. NAME OF OPERATOR  
J. M. Huber Corporation

3. ADDRESS OF OPERATOR  
1050 17th Street, Ste 700 Denver, CO 80265

PHONE NUMBER  
303-825-7900

4. LOCATION OF WELL (FOOTAGES)

330' FNL, 1520' FWL

AT TOP PRODUCING INTERVAL REPORTED BELOW:

Same

AT TOTAL DEPTH:

Same

14. DATE SPUNDED: 7/29/01  
15. DATE T.D. REACHED: 9/20/01  
16. DATE COMPLETED: 11/11/01

ABANDONED ☐

READY TO PRODUCE ☒

17. ELEVATIONS (DF, RKB, RT, GL):  
7240 GR, 7253' KB

18. TOTAL DEPTH: MD

5180' KB

TVD

5180' KB

19. PLUG BACK T.D.: MD

5162' KB

TVD

5162' KB

20. IF MULTIPLE COMPLETIONS, HOW MANY?

21. DEPTH BRIDGE MD

PLUG SET:

TVD

22. TYPE ELECTRIC AND OTHER MECHANICAL LOGS RUN (Submit copy of each)

RST-GR, CBL-GR - 11-20-01

23. WAS WELL CORED?

NO ☒

YES ☐

(Submit analysis)

WAS DST RUN?

NO ☒

YES ☐

(Submit report)

DIRECTIONAL SURVEY?

NO ☒

YES ☐

(Submit copy)

24. CASING AND LINER RECORD (Report all strings set in well)

HOLE SIZE	SIZE/GRADE	WEIGHT (#/FT.)	TOP (MD)	BOTTOM (MD)	STAGE CEMENTER DEPTH	CEMENT TYPE & NO. OF SACKS	SLURRY VOLUME (BBL)	CEMENT TOP**	AMOUNT PULLED
17-1/2"	13-3/8"		Surf.	14'				Surf	
12-1/4"	8-5/8" J-55	24	Surf.	513' GL	513' GL	G 350	75	Surf	
7-7/8"	5-1/2" J-55	17	Surf.	5172' KB	5172' KB	Class G 170	36	4314' KB	
					4314' KB	H.L.C. 400	130	2870'	

25. TUBING RECORD

SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)
2-7/8"	4838' KB							

26. PRODUCING INTERVALS

FORMATION NAME	TOP (MD)	BOTTOM (MD)	TOP (TVD)	BOTTOM (TVD)	INTERVAL (Top/Bot - MD)	SIZE	NO. HOLES	PERFORATION STATUS
(A) Aberdeen Coal	4936' KB	5116' KB			4936'-4935', 4957'-		140	OPEN <input checked="" type="checkbox"/> SQUEEZED
(B) (BLK H / BGR)					4960', 4984'-4991'			OPEN <input checked="" type="checkbox"/> SQUEEZED
(C)					5024'-5030', 5096'-			OPEN <input checked="" type="checkbox"/> SQUEEZED
(D)					5100', 5110'-5116'			OPEN <input checked="" type="checkbox"/> SQUEEZED

28. ACID, FRACTURE, TREATMENT, CEMENT SQUEEZE, ETC.

DEPTH INTERVAL	AMOUNT AND TYPE OF MATERIAL
4936' to 5116' KB	900 gal 15% HCl
4936' to 5116' KB	1620 bbl Delta Frac 140 with 2007 sacks 20/40 sand

29. ENCLOSED ATTACHMENTS:

☐ ELECTRICAL/MECHANICAL LOGS

☐ GEOLOGIC REPORT

☐ DST REPORT

☐ DIRECTIONAL SURVEY

☐ SUNDRY NOTICE FOR PLUGGING AND CEMENT VERIFICATION

☐ CORE ANALYSIS

☐ OTHER: \_\_\_\_\_

30. WELL STATUS:

RECEIVED

(CONTINUED ON BACK)

DEC 24 2001

DIVISION OF  
OIL, GAS AND MINING

## 31. INITIAL PRODUCTION

## INTERVAL A (As shown in Item #26)

DATE FIRST PRODUCED: 11/2/01		TEST DATE 11/3/01		HOURS TESTED: 24		TEST PRODUCTION RATES: →	OIL - BBL: 0	GAS - MCF: 20	WATER - BBL: 698	PROD. METHOD: Rod Pump
CHOKE SIZE:	TBG. PRESS. 110	CSG. PRESS 950	API GRAVITY	BTU - GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL - BBL: 0	GAS - MCF: 20	WATER - BBL: 698	INTERVAL STATUS: Producing

## INTERVAL B (As shown in Item #26)

DATE FIRST PRODUCED:		TEST DATE		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL - BBL:	GAS - MCF:	WATER - BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS	API GRAVITY	BTU - GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL - BBL:	GAS - MCF:	WATER - BBL:	INTERVAL STATUS:

## INTERVAL C (As shown in Item #26)

DATE FIRST PRODUCED:		TEST DATE		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL - BBL:	GAS - MCF:	WATER - BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS	API GRAVITY	BTU - GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL - BBL:	GAS - MCF:	WATER - BBL:	INTERVAL STATUS:

## INTERVAL D (As shown in Item #26)

DATE FIRST PRODUCED:		TEST DATE		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL - BBL:	GAS - MCF:	WATER - BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS	API GRAVITY	BTU - GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL - BBL:	GAS - MCF:	WATER - BBL:	INTERVAL STATUS:

## 32. DISPOSITION OF GAS (Sold, Used for Fuel, Vented, Etc.)

Vented pending pipeline hookup

## 33. SUMMARY OF POROUS ZONES (Include Aquifers):

Show all important zones of porosity and contents thereof. Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open flowing and shut-in pressures and recoveries.

## 34. FORMATION (Log) MARKERS:

Formation	Top (MD)	Bottom (MD)	Descriptions, Contents, etc.	Name	Top (Measured Depth)
Price River	2913	3485	Water		
Castlegate	3485	4231	Water		
Blackhawk	4231	5074	Water and Gas in Coals		
Aberdeen SS	5074	TD	Water		

## 35. ADDITIONAL REMARKS (include plugging procedure)

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records.


NAME (PLEASE PRINT)

Gary J. Johnson

TITLE

Consulting Petroleum Engineer

SIGNATURE



DATE

12/18/01

This report must be submitted within 30 days of

- completing or plugging a new well
- drilling horizontal laterals from an existing well bore
- recompleting to a different producing formation
- reentering a previously plugged and abandoned well
- significantly deepening an existing well bore below the previous bottom-hole depth
- drilling hydrocarbon exploratory holes, such as core samples and stratigraphic tests

\* Item 20: Show the number of completions if production is measured separately from two or more formations.

\*\* Item 24: Cement Top - Show how reported top(s) of cement were determined (circulated (CIR), calculated (CAL), cement bond log (CBL), temperature survey (TS)).

Send to: Utah Division of Oil, Gas and Mining  
1594 West North Temple, Suite 1210  
Box 145801  
Salt Lake City, Utah 84114-5801

Phone: 801-538-5340

Fax: 801-359-3940





A FAMILY OF SOLUTIONS

RECEIVED

JAN 14 2002

DIVISION OF  
OIL, GAS AND MINING

ENERGY

J.M. Huber Corporation

1050 17<sup>th</sup> St., Ste. 700  
Denver, CO 80265

phone: (303) 825-7900  
fax: (303) 825-8300  
e-mail: dv\_cpjaw@huber.cc  
www.huber.com

January 9, 2002

Utah Division of Oil, Gas and Mining  
Carol Daniels  
1594 West North Temple, Suite 1210  
Box 145801  
Salt Lake City, UT 84114

RE: Form 8, Completion Report – Corrected  
Huber-Jensen 2-9, NENW Sec. 9, T12S, R10E, API # 43-007-30735 – **Corrected Completion Date**  
Huber-Shimmin Trust 4-14, SWNW Sec. 14, T12S, R10E, API# 43-007-30662 – **Corrected Spud & Completion Date**  
Huber-Jensen 1-8, NESE Sec. 8, T12S, R10E, API # 43-007-30768 – **Corrected Spud Date**  
Huber-Jensen 1-4, SWSE Sec. 4, T12S, R10E, API # 43-007-30733 – **Corrected Spud date & Completion Date**

Dear Carol,

Enclosed you will find the CORRECTED Form 8's for the above-mentioned wells. If you have any other questions or concerns please do not hesitate to call me at 303-825-7900.

Respectfully yours,

Judith A. Walter  
Regulatory Compliance – Contract Agent

Cc: J.M. Huber Field Office – Larry Sessions, 212 East 100 North, PO Box 551, Price, UT 84501  
Patina Oil & Gas Corp., 1625 Broadway, Suite 2000, Denver, CO 80202  
Correspondence  
Well File – 3 (Tom Erwin, Gary Johnson, WF)

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

AMENDED REPORT ☒ FORM 8  
(highlight changes)

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

1a. TYPE OF WELL: OIL WELL ☐ GAS WELL ☒ DRY ☐ OTHER \_\_\_\_\_  
b. TYPE OF WORK  
NEW ☒ HORIZ. ☐ DEEP- ☐ RE- ☐ DIFF. ☐

2. NAME OF OPERATOR  
J. M. Huber Corporation

3. ADDRESS OF OPERATOR  
1050 17th Street, Ste 700 Denver, CO 80265

PHONE NUMBER  
303-825-7900

4. LOCATION OF WELL (FOOTAGES)  
330' FNL, 1520' FWL

AT TOP PRODUCING INTERVAL REPORTED BELOW: Same

AT TOTAL DEPTH: Same

14. DATE SPUNDED: 7/29/01 15. DATE T.D. REACHED: 9/20/01 16. DATE COMPLETED: 11/02/2001  
ABANDONED ☐ READY TO PRODUCE ☒

17. ELEVATIONS (DF, RKB, RT, GL):  
7240 GR, 7253' KB

18. TOTAL DEPTH: MD 5180' KB TVD 5180' KB  
19. PLUG BACK T.D.: MD 5162' KB TVD 5162' KB  
20. IF MULTIPLE COMPLETIONS, HOW MANY? \*  
21. DEPTH BRIDGE MD PLUG SET: TVD

22. TYPE ELECTRIC AND OTHER MECHANICAL LOGS RUN (Submit copy of each)  
RST -GR, CBL-GR

23. WAS WELL CORED? NO ☒ YES ☐ (Submit analysis)  
WAS DST RUN? NO ☒ YES ☐ (Submit report)  
DIRECTIONAL SURVEY? NO ☒ YES ☐ (Submit copy)

24. CASING AND LINER RECORD (Report all strings set in well)

HOLE SIZE	SIZE/GRADE	WEIGHT (#/FT.)	TOP (MD)	BOTTOM (MD)	STAGE CEMENTER DEPTH	CEMENT TYPE & NO. OF SACKS	SLURRY VOLUME (BBL)	CEMENT TOP**	AMOUNT PULLED
17-1/2"	13-3/8"		Surf.	14'				Surf	
12-1/4"	8-5/8" J-55	24	Surf.	513' GL	513' GL	G 350	75	Surf	
7-7/8"	5-1/2" J-55	17	Surf.	5172' KB	5172' KB	Class G 170	36	4314' KB	
					4314' KB	H.L.C. 400	130	2870'	

25. TUBING RECORD

SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)
2-7/8"	4838' KB							

26. PRODUCING INTERVALS

FORMATION NAME	TOP (MD)	BOTTOM (MD)	TOP (TVD)	BOTTOM (TVD)	INTERVAL (Top/Bot - MD)	SIZE	NO. HOLES	PERFORATION STATUS
(A) Aberdeen Coal	4936' KB	5116' KB			4936'-4935', 4957'-		140	OPEN <input checked="" type="checkbox"/> SQUEEZED
(B)					4960', 4984'-4991',			OPEN <input checked="" type="checkbox"/> SQUEEZED
(C)					5024'-5030', 5096'-			OPEN <input checked="" type="checkbox"/> SQUEEZED
(D)					5100', 5110'-5116'			OPEN <input checked="" type="checkbox"/> SQUEEZED

28. ACID, FRACTURE, TREATMENT, CEMENT SQUEEZE, ETC.

DEPTH INTERVAL	AMOUNT AND TYPE OF MATERIAL
4936' to 5116' KB	900 gal 15% HCl
4936' to 5116' KB	1620 bbl Delta Frac 140 with 2007 sacks 20/40 sand

29. ENCLOSED ATTACHMENTS:

☐ ELECTRICAL/MECHANICAL LOGS ☐ GEOLOGIC REPORT ☐ DST REPORT ☐ DIRECTIONAL SURVEY  
☐ SUNDRY NOTICE FOR PLUGGING AND CEMENT VERIFICATION ☐ CORE ANALYSIS ☐ OTHER: \_\_\_\_\_

30. WELL STATUS:

RECEIVED

(CONTINUED ON BACK)

JAN 14 2002

DIVISION OF  
OIL, GAS AND MINING

## 31. INITIAL PRODUCTION

## INTERVAL A (As shown in Item #26)

DATE FIRST PRODUCED:		TEST DATE		HOURS TESTED:		TEST PRODUCTION	OIL - BBL:	GAS - MCF:	WATER - BBL:	PROD. METHOD:
11/2/01		11/3/01		24		RATES: →	0	20	698	Rod Pump
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS	API GRAVITY	BTU - GAS	GAS/OIL RATIO	24 HR PRODUCTION	OIL - BBL:	GAS - MCF:	WATER - BBL:	INTERVAL STATUS:
	110	950				RATES: →	0	20	698	Producing

## INTERVAL B (As shown in Item #26)

DATE FIRST PRODUCED:		TEST DATE		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL - BBL:	GAS - MCF:	WATER - BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS	API GRAVITY	BTU - GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL - BBL:	GAS - MCF:	WATER - BBL:	INTERVAL STATUS:

## INTERVAL C (As shown in Item #26)

DATE FIRST PRODUCED:		TEST DATE		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL - BBL:	GAS - MCF:	WATER - BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS	API GRAVITY	BTU - GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL - BBL:	GAS - MCF:	WATER - BBL:	INTERVAL STATUS:

## INTERVAL D (As shown in Item #26)

DATE FIRST PRODUCED:		TEST DATE		HOURS TESTED:		TEST PRODUCTION	OIL - BBL:	GAS - MCF:	WATER - BBL:	PROD. METHOD:
						RATES: →				
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS	API GRAVITY	BTU - GAS	GAS/OIL RATIO	24 HR PRODUCTION	OIL - BBL:	GAS - MCF:	WATER - BBL:	INTERVAL STATUS:
						RATES: →				

## 32. DISPOSITION OF GAS (Sold, Used for Fuel, Vented, Etc.)

Vented pending pipeline hookup

## 33. SUMMARY OF POROUS ZONES (Include Aquifers):

Show all important zones of porosity and contents thereof: Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open flowing and shut-in pressures and recoveries.

## 34. FORMATION (Log) MARKERS:

Formation	Top (MD)	Bottom (MD)	Descriptions, Contents, etc.	Name	Top (Measured Depth)
Price River	2913	3485	Water		
Castlegate	3485	4231	Water		
Blackhawk	4231	5074	Water and Gas in Coals		
Aberdeen SS	5074	TD	Water		


## 35. ADDITIONAL REMARKS (Include plugging procedure)

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records.

NAME (PLEASE PRINT) Gary J. Johnson

TITLE Consulting Petroleum Engineer

SIGNATURE



DATE 1/2/02

This report must be submitted within 30 days of

- completing or plugging a new well
- reentering a previously plugged and abandoned well
- drilling horizontal laterals from an existing well bore
- significantly deepening an existing well bore below the previous bottom-hole depth
- recompleting to a different producing formation
- drilling hydrocarbon exploratory holes, such as core samples and stratigraphic tests

\* Item 20: Show the number of completions if production is measured separately from two or more formations.

\*\* Item 24: Cement Top - Show how reported top(s) of cement were determined (circulated (CIR), calculated (CAL), cement bond log (CBL), temperature survey (TS)).

Send to: Utah Division of Oil, Gas and Mining  
1594 West North Temple, Suite 1210  
Box 145801  
Salt Lake City, Utah 84114-5801

Phone: 801-538-5340

Fax: 801-359-3940

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

**SUNDRY NOTICES AND REPORTS ON WELLS**

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: Private-Fee
2. NAME OF OPERATOR: J. M. Huber Corp.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: NA
3. ADDRESS OF OPERATOR: 1050 17th St, Ste. 700 CITY Denver STATE CO ZIP 80265		7. UNIT or CA AGREEMENT NAME: NA
4. LOCATION OF WELL FOOTAGES AT SURFACE: 330' FNL, 1520' FWL		8. WELL NAME and NUMBER: Huber Jensen 2-9
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NENW 9 12S 10E S		9. API NUMBER: 43-7-30735
COUNTY: Carbon		10. FIELD AND POOL, OR WILDCAT: Castlegate
STATE: UTAH		

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input checked="" type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

See Attached Sheet.

NAME (PLEASE PRINT) Robert F. Unger TITLE V. P.-Northern Business Unit of J. M. Huber Corp.

SIGNATURE *Robert F. Unger* DATE 11/20/03

(This space for State use only)

RECEIVED  
JAN 22 2004 1890-116  
DIV. OF OIL, GAS & MINING

Attachment for the State of Utah, Department of Natural Resources, Division of Oil, Gas and Mining, Form 9, Sundry Notices and Reports on Wells:

Huber Jensen 2-9

J. M. Huber Corporation has sold its interests in this well and property. The new owner will be taking on the responsibility of operator.

Name (please print) Robert F. Unger

Title: V. P.-Northern Business Unit

Signature: 

Date: 11/20/03

New owner information:

Company Name: Evergreen Operating Corp., 1401 17th Street, Suite 1200  
Denver, CO 80202

Name (please print) Kevin D. Davis

Title: Director - Mergers & Acquisitions

Signature: 

Date: 1/15/2004

New owner bond number: RLB 000 6706

## OPERATOR CHANGE WORKSHEET

## ROUTING

1. GLH

2. CDW

3. FILE

X Change of Operator (Well Sold)

Designation of Agent/Operator

Operator Name Change

Merger

The operator of the well(s) listed below has changed, effective:

12/1/2003

**FROM:** (Old Operator):

N2380-J.M. Huber Corp  
1050 17th St, Ste. 700  
Denver, CO 80265

Phone: 1-(303) 825-7900

**TO:** ( New Operator):

N2545-Evergreen Operating Corp.  
1401 17th Street, Suite 1200  
Denver, CO 80202

Phone: 1-(303) 298-8100

CA No.

Unit:

**WELL(S)**

NAME	SEC	TWN	RNG	API NO	ENTITY NO	LEASE TYPE	WELL TYPE	WELL STATUS
HUBER-JENSEN 1-4	04	120S	100E	4300730733	13068	Fee	GW	P
HUBER-JENSEN 2-8	08	120S	100E	4300730734	13275	Fee	GW	P
HUBER-JENSEN 1-8	08	120S	100E	4300730768	13359	Fee	GW	P
HUBER-JENSEN 16-9	09	120S	100E	4300730163	12904	Fee	GW	P
HUBER-JENSEN 1-9	09	120S	100E	4300730717	12903	Fee	GW	P
HUBER-JENSEN 2-9	09	120S	100E	4300730735	13317	Fee	GW	P
HUBER-JENSEN 9-10	10	120S	100E	4300730159	12906	Fee	GW	P
HUBER-JENSEN 5-10	10	120S	100E	4300730162	12905	Fee	GW	P
HUBER-JENSEN 1-10	10	120S	100E	4300730596	12611	Fee	GW	P
HUBER-SHIMMIN TRUST 2-11	11	120S	100E	4300730659	13070	Fee	GW	P
HUBER-SHIMMIN TRUST 1-11	11	120S	100E	4300730673	12901	Fee	GW	P
HUBER-SHIMMIN TRUST 1-12	12	120S	100E	4300730674	12902	Fee	GW	P
HUBER-SHIMMIN TRUST 3-14	14	120S	100E	4300730640	13069	Fee	GW	P
HUBER-SHIMMIN TRUST 4-14	14	120S	100E	4300730662	13071	Fee	GW	P
HUBER-JENSEN 1-15	15	120S	100E	4300730736	13072	Fee	GW	P
HUBER-STATE 1-16	16	120S	100E	4300730589	12610	State	GW	P
HUBER-ST 4-16	16	120S	100E	4300730785	13318	State	GW	P

## OPERATOR CHANGES DOCUMENTATION

Enter date after each listed item is completed

1. (R649-8-10) Sundry or legal documentation was received from the **FORMER** operator on: 1/22/2004
2. (R649-8-10) Sundry or legal documentation was received from the **NEW** operator on: 1/22/2004
3. The new company was checked on the **Department of Commerce, Division of Corporations Database** on: 12/29/2003
4. Is the new operator registered in the State of Utah: YES Business Number: 5531527-0143
5. If NO, the operator was contacted contacted on: \_\_\_\_\_

6. (R649-9-2)Waste Management Plan has been received on:

In Place

7. **Federal and Indian Lease Wells:** The BLM and or the BIA has approved the merger, name change, or operator change for all wells listed on Federal or Indian leases on: BLM BIA

8. **Federal and Indian Units:**

The BLM or BIA has approved the successor of unit operator for wells listed on: n/a

9. **Federal and Indian Communization Agreements ("CA"):**

The BLM or BIA has approved the operator for all wells listed within a CA on: n/a

10. **Underground Injection Control ("UIC")** The Division has approved UIC Form 5, Transfer of Authority to Inject, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on: N/A

**DATA ENTRY:**

1. Changes entered in the Oil and Gas Database on: 1/28/2004
2. Changes have been entered on the Monthly Operator Change Spread Sheet on: 1/28/2004
3. Bond information entered in RBDMS on: N/A
4. Fee wells attached to bond in RBDMS on: N/A
5. Injection Projects to new operator in RBDMS on: n/a

**STATE WELL(S) BOND VERIFICATION:**

1. State well(s) covered by Bond Number: RLB0006732

**FEDERAL WELL(S) BOND VERIFICATION:**

1. Federal well(s) covered by Bond Number: n/a

**INDIAN WELL(S) BOND VERIFICATION:**

1. Indian well(s) covered by Bond Number: n/a

**FEE WELL(S) BOND VERIFICATION:**

1. (R649-3-1) The NEW operator of any fee well(s) listed covered by Bond Number RLB0006706
2. The FORMER operator has requested a release of liability from their bond on: N/A  
The Division sent response by letter on: N/A

**LEASE INTEREST OWNER NOTIFICATION:**

3. (R649-2-10) The FORMER operator of the fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: N/A

**COMMENTS:**

**STATE OF UTAH**  
**DEPARTMENT OF NATURAL RESOURCES**  
**DIVISION OF OIL, GAS AND MINING**

<p align="center"><b>SUNDRY NOTICES AND REPORTS ON WELLS</b></p> <p>Do not use this form for proposals to drill new wells, deepen existing wells, or to reenter plugged and abandoned wells.          Use APPLICATION FOR PERMIT – for such proposals</p>		6. Lease Designation and Serial Number <i>Fee</i>
		7. Indian Allottee or Tribe Name <i>na</i>
		8. Unit or Communitization Agreement <i>na</i>
1. Type of Well <input type="checkbox"/> Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other (specify) <i>2</i>		9. Well Name and Number <i>Huber Jensen 2-9</i>
2. Name of Operator <i>Evergreen Operating Corporation</i>		10. API Well Number <i>43-007-30735</i>
3. Address of Operator <i>1401 17th St., Suite 1200, Denver, Colorado 80202</i>	4. Telephone Number <i>303-298-8100</i>	11. Field and Pool, or Wildcat <i>Castlegate</i>
5. Location of Well Footage : 330' FNL & 1520' FWL     County : <i>Carbon</i> QQ, Sec. T., R., M : <i>nenw, Section 9, T12S-R10E</i> State : <i>Utah</i>		
12. <b>CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA</b>		

**NOTICE OF INTENT**  
 (Submit in Duplicate)

- |   |   |
|---|---|
| <input type="checkbox"/> Abandonment                              | <input type="checkbox"/> New Construction     |
| <input type="checkbox"/> Casing Repair                            | <input type="checkbox"/> Pull or Alter Casing |
| <input type="checkbox"/> Change of Plans                          | <input type="checkbox"/> Recompletion         |
| <input type="checkbox"/> Conversion to Injection                  | <input type="checkbox"/> Shoot or Acidize     |
| <input checked="" type="checkbox"/> Fracture Treat                | <input type="checkbox"/> Vent or Flare        |
| <input type="checkbox"/> Multiple Completion                      | <input type="checkbox"/> Water Shut-Off       |
| <input checked="" type="checkbox"/> Other <i>add perforations</i> |   |

Approximate Date Work Will Start May 12, 2004

**SUBSEQUENT REPORT**  
 (Submit Original Form Only)

- |  |   |
|--|---|
| <input type="checkbox"/> Abandonment *           | <input type="checkbox"/> New Construction     |
| <input type="checkbox"/> Casing Repair           | <input type="checkbox"/> Pull or Alter Casing |
| <input type="checkbox"/> Change of Plans         | <input type="checkbox"/> Shoot or Acidize     |
| <input type="checkbox"/> Conversion to Injection | <input type="checkbox"/> Vent or Flare        |
| <input type="checkbox"/> Fracture Treat          | <input type="checkbox"/> Water Shut-Off       |
| <input type="checkbox"/> Other                   |   |

Date of Work Completion \_\_\_\_\_

Report results of Multiple Completions and Recompletions to different reservoirs on WELL COMPLETION OR RECOMPLETION AND LOG form.

\* Must be accompanied by a cement verification report.

13. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

*Evergreen Operating Corporation intends to add perforations in the upper Blackhawk Coal Formation and fracture stimulate the same using coiled tubing. The existing perforated interval is 4760' - 4764', 4936' - 4945', 4957' - 4960', 4984' - 4991', 5024' - 5030', 5096' - 5100', and 5110' - 5116'. The additional perforations that will be added are 4706' - 4710', 4834' - 4836', and 4845' - 4849'. Tubing, rods, and pump will be run in the hole and the well returned to production.*

COPY SENT TO OPERATOR

Date: 4-30-04  
 Initials: CHO

14. I hereby certify that the foregoing is true and correct.

Name & Signature Todd S. McDonald *Todd S. McDonald*

Title Director of Operations Date 04/22/04

(State Use Only)

APPROVED BY THE STATE  
 OF UTAH DIVISION OF  
 OIL, GAS AND MINING

(8/90)

*4/29/04*  
*D. S. McDonald*

See Instructions on Reverse Side

**RECEIVED**

**APR 28 2004**

DIV. OF OIL, GAS & MINING



## OPERATOR CHANGE WORKSHEET

## ROUTING

1. GLH

2. CDW

3. FILE

Change of Operator (Well Sold)

Designation of Agent/Operator

Operator Name Change

**X Merger**

The operator of the well(s) listed below has changed, effective:

**9/28/2004****FROM: (Old Operator):**

N2545-Evergreen Operating Corp.

1401 17th St, Suite 1200

Denver, CO 80202

Phone: 1-(303) 298-8100

**TO: ( New Operator):**

N5155-Pioneer Natural Resources USA, Inc.

5205 N O'Connor Blvd

Irving, TX 75039

Phone: 1-(972) 444-9001

**CA No.****Unit:****WELL(S)**

NAME	SEC	TWN	RNG	API NO	ENTITY NO	LEASE TYPE	WELL TYPE	WELL STATUS
HUBER-ST 1-35	35	110S	100E	4301332308	13472	State	WD	A
HUBER-JENSEN 1-4	04	120S	100E	4300730733	13068	Fee	GW	P
HUBER-JENSEN 2-8	08	120S	100E	4300730734	13275	Fee	GW	P
HUBER-JENSEN 1-8	08	120S	100E	4300730768	13359	Fee	GW	P
HUBER-JENSEN 2-9	09	120S	100E	4300730735	13317	Fee	GW	P
SHIMMIN 11-14	14	120S	100E	4300730962	14223	Fee	GW	DRL K
HUBER-JENSEN 1-15	15	120S	100E	4300730736	13072	Fee	GW	P
JENSON 7-15 DEEP	15	120S	100E	4300730786	13247	Fee	GW	TA
HUBER-STATE 1-16	16	120S	100E	4300730589	12610	State	GW	P
HUBER-ST 4-16	16	120S	100E	4300730785	13318	State	GW	P
STATE 11-16	16	120S	100E	4300730961	14224	State	GW	DRL K
HUBER-JENSEN 1-18	18	120S	100E	4300730718	14226	Fee	GW	DRL
PINE SPRINGS ST 6-36-14-22	36	140S	220E	4304735555	14352	State	GW	DRL K
STATE 8-2-15-22	02	150S	220E	4304731135	8076	State	GW	S
PINE SPRINGS FED 12-23-14S-22E	23	140S	220E	4304734676	13616	Federal	GW	TA K

**OPERATOR CHANGES DOCUMENTATION**

Enter date after each listed item is completed

1. (R649-8-10) Sundry or legal documentation was received from the **FORMER** operator on: 10/21/2004
2. (R649-8-10) Sundry or legal documentation was received from the **NEW** operator on: 10/21/2004

3. The new company was checked on the **Department of Commerce, Division of Corporations Database** on: 10/21/2004
4. Is the new operator registered in the State of Utah: YES Business Number: 5738462-0143
5. If **NO**, the operator was contacted on: \_\_\_\_\_

6a. (R649-9-2) Waste Management Plan has been received on: \_\_\_\_\_

6b. Inspections of LA PA state/fee well sites complete on: \_\_\_\_\_

\*\*\*

7. **Federal and Indian Lease Wells:** The BLM and or the BIA has approved the merger, name change, or operator change for all wells listed on Federal or Indian leases on: not yet

8. **Federal and Indian Units:**

The BLM or BIA has approved the successor of unit operator for wells listed on: \_\_\_\_\_

9. **Federal and Indian Communization Agreements ("CA"):**

The BLM or BIA has approved the operator for all wells listed within a CA on: \_\_\_\_\_

10. **Underground Injection Control ("UIC")** The Division has approved UIC Form 5, **Transfer of Authority to Inject**, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on: N/A

**DATA ENTRY:**

1. Changes entered in the Oil and Gas Database on: 10/28/2004
2. Changes have been entered on the Monthly Operator Change Spread Sheet on: 10/28/2004
3. Bond information entered in RBDMS on: 10/28/2004
4. Fee/State wells attached to bond in RBDMS on: 10/28/2004
5. Injection Projects to new operator in RBDMS on: 10/28/2004
6. Receipt of Acceptance of Drilling Procedures for APD/New on: \*\*\*

**FEDERAL WELL(S) BOND VERIFICATION:**

1. Federal well(s) covered by Bond Number: 104091293

**INDIAN WELL(S) BOND VERIFICATION:**

1. Indian well(s) covered by Bond Number: n/a

**FEE & STATE WELL(S) BOND VERIFICATION:**

1. (R649-3-1) The **NEW** operator of any fee well(s) listed covered by Bond Number 104319462
2. The **FORMER** operator has requested a release of liability from their bond on: 10/21/2004  
The Division sent response by letter on: 10/28/2004

**LEASE INTEREST OWNER NOTIFICATION:**

3. (R649-2-10) The **FORMER** operator of the fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: 11/1/2004

**COMMENTS:**

**STATE OF UTAH**  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

**SUNDRY NOTICES AND REPORTS ON WELLS**

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER:
2. NAME OF OPERATOR: Pioneer Natural Resources USA, Inc. <i>N5155</i>		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: 5205 N. O'Connor Blvd CITY Irving STATE TX ZIP 75039		7. UNIT or CA AGREEMENT NAME:
PHONE NUMBER: (972) 444-9001		8. WELL NAME and NUMBER: See Attached List
4. LOCATION OF WELL FOOTAGES AT SURFACE: _____ COUNTY: _____ QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: _____ STATE: <b>UTAH</b>		9. API NUMBER:
		10. FIELD AND POOL, OR WILDCAT:

**11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA**

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate)  Approximate date work will start: _____  <input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only)  Date of work completion: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input checked="" type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

1. Operator change due to the merger between Pioneer Natural Resources USA, Inc and Evergreen Resources Inc., effective September 28, 2004.
2. See list attached for all wells currently operated under the name of Evergreen Operating (subsidiary of Evergreen Resources) as listed on the DOGM database on October 15, 2004.
3. Operator will now be Pioneer Natural Resources USA, Inc. Local operation address info and contacts under separate cover.
4. Surety Bond #104319462 (replaces RLB 0006706) attached
5. Copy of Oil & Gas Geothermal Lease Bond - BLM #104091293 attached

Name: Dennis R. Carlton

Title: Executive Vice President, Evergreen Operating Corp. *N2545*

Signature: *DR Carlton*

Date: *10/18/04*

NAME (PLEASE PRINT) Jay Still

TITLE Vice President, Western Division, Pioneer Natural Resources USA Inc.

SIGNATURE *Jay Still*

DATE *10/19/04*

(This space for State use only)

**APPROVED** *10/28/04*  
*Earlene Russell*  
Division of Oil, Gas and Mining  
Earlene Russell, Engineering Technician

(5/2000)

(See Instructions on Reverse Side)

**RECEIVED**  
**OCT 21 2004**  
DIV. OF OIL, GAS & MINING

**EVERGREEN TO PIONEER NATURAL RESOURCES USA, INC. MERGER**  
**WELL LIST 10/15/04**

API Well Number	Operator	Well Name	Well Type	Well Status	Field Name	County Name	Location (Twn-Rng)	Sect	Twpn	Twpd	RngN	RngD	Qtr/Qtr
43-007-30122-00-00	EVERGREEN OPERATING CORP	SHIMMIN TRUST 5	Gas Well	Producing	CASTLEGATE	CARBON	12S-10E	14	12	S	10	E	NWNE
43-007-30137-00-00	EVERGREEN OPERATING CORP	HUBER-FEDERAL 7-9	Gas Well	Producing	CASTLEGATE	CARBON	12S-10E	9	12	S	10	E	SWNE
43-007-30138-00-00	EVERGREEN OPERATING CORP	HUBER-FRANSEN 4-15	Gas Well	Plugged and Abandoned	CASTLEGATE	CARBON	12S-10E	15	12	S	10	E	NWNW
43-007-30140-00-00	EVERGREEN OPERATING CORP	HUBER-FED 6-8	Gas Well	Plugged and Abandoned	CASTLEGATE	CARBON	12S-10E	8	12	S	10	E	SENW
43-007-30159-00-00	EVERGREEN OPERATING CORP	HUBER-JENSEN 9-10	Gas Well	Producing	CASTLEGATE	CARBON	12S-10E	10	12	S	10	E	NESE
43-007-30162-00-00	EVERGREEN OPERATING CORP	HUBER-JENSEN 5-10	Gas Well	Producing	CASTLEGATE	CARBON	12S-10E	10	12	S	10	E	SWNW
43-007-30163-00-00	EVERGREEN OPERATING CORP	HUBER-JENSEN 16-9	Gas Well	Producing	CASTLEGATE	CARBON	12S-10E	9	12	S	10	E	SESE
43-007-30164-00-00	EVERGREEN OPERATING CORP	HUBER-JENSEN 11-10	Gas Well	Producing	CASTLEGATE	CARBON	12S-10E	10	12	S	10	E	NESW
				Spudded (Drilling commenced: Not yet completed)									
43-007-30166-00-00	EVERGREEN OPERATING CORP	SHIMMIN TRUST 11-11	Gas Well		CASTLEGATE	CARBON	12S-10E	11	12	S	10	E	NESW
43-007-30169-00-00	EVERGREEN OPERATING CORP	SHIMMIN TRUST 14-12	Gas Well	Plugged and Abandoned	CASTLEGATE	CARBON	12S-10E	12	12	S	10	E	SESW
43-007-30589-00-00	EVERGREEN OPERATING CORP	HUBER-STATE 1-16	Gas Well	Producing	CASTLEGATE	CARBON	12S-10E	16	12	S	10	E	NWNE
43-007-30596-00-00	EVERGREEN OPERATING CORP	HUBER-JENSEN 1-10	Gas Well	Producing	CASTLEGATE	CARBON	12S-10E	10	12	S	10	E	NWSW
43-007-30640-00-00	EVERGREEN OPERATING CORP	HUBER-SHIMMIN TRUST 3-14	Gas Well	Producing	CASTLEGATE	CARBON	12S-10E	14	12	S	10	E	SENE
43-007-30659-00-00	EVERGREEN OPERATING CORP	HUBER-SHIMMIN TRUST 2-11	Gas Well	Producing	CASTLEGATE	CARBON	12S-10E	11	12	S	10	E	SESE
43-007-30662-00-00	EVERGREEN OPERATING CORP	HUBER-SHIMMIN TRUST 4-14	Gas Well	Producing	CASTLEGATE	CARBON	12S-10E	14	12	S	10	E	SENW
<del>43-007-30663-00-00</del>	<del>EVERGREEN OPERATING CORP</del>	<del>HUBER-ST 4-11</del>	<del>Gas Well</del>	<del>Location Abandoned</del>	<del>CASTLEGATE</del>	<del>CARBON</del>	<del>12S-10E</del>	<del>11</del>	<del>12</del>	<del>S</del>	<del>10</del>	<del>E</del>	<del>SE</del>
43-007-30673-00-00	EVERGREEN OPERATING CORP	HUBER-SHIMMIN TRUST 1-11	Gas Well	Producing	CASTLEGATE	CARBON	12S-10E	11	12	S	10	E	SE
43-007-30674-00-00	EVERGREEN OPERATING CORP	HUBER-SHIMMIN TRUST 1-12	Gas Well	Producing	CASTLEGATE	CARBON	12S-10E	12	12	S	10	E	NWSW
				Spudded (Drilling commenced: Not yet completed)									
43-007-30675-00-00	EVERGREEN OPERATING CORP	HUBER-JENSEN 2-10	Gas Well		CASTLEGATE	CARBON	12S-10E	10	12	S	10	E	NESE
<del>43-007-30676-00-00</del>	<del>EVERGREEN OPERATING CORP</del>	<del>HUBER-JENSEN 3-10</del>	<del>Gas Well</del>	<del>Location Abandoned</del>	<del>CASTLEGATE</del>	<del>CARBON</del>	<del>12S-10E</del>	<del>10</del>	<del>12</del>	<del>S</del>	<del>10</del>	<del>E</del>	<del>SWNE</del>
43-007-30717-00-00	EVERGREEN OPERATING CORP	HUBER-JENSEN 1-9	Gas Well	Producing	CASTLEGATE	CARBON	12S-10E	9	12	S	10	E	NWSW
				Spudded (Drilling commenced: Not yet completed)									
43-007-30718-00-00	EVERGREEN OPERATING CORP	HUBER-JENSEN 1-18	Gas Well		CASTLEGATE	CARBON	12S-10E	18	12	S	10	E	NESE
43-007-30733-00-00	EVERGREEN OPERATING CORP	HUBER-JENSEN 1-4	Gas Well	Producing	CASTLEGATE	CARBON	12S-10E	4	12	S	10	E	SWSE
43-007-30734-00-00	EVERGREEN OPERATING CORP	HUBER-JENSEN 2-8	Gas Well	Producing	CASTLEGATE	CARBON	12S-10E	8	12	S	10	E	NENE
43-007-30735-00-00	EVERGREEN OPERATING CORP	HUBER-JENSEN 2-9	Gas Well	Producing	CASTLEGATE	CARBON	12S-10E	9	12	S	10	E	NENW
43-007-30736-00-00	EVERGREEN OPERATING CORP	HUBER-JENSEN 1-15	Gas Well	Producing	CASTLEGATE	CARBON	12S-10E	15	12	S	10	E	SWNE
43-007-30764-00-00	EVERGREEN OPERATING CORP	HUBER-JF 2-17	Gas Well	New Permit (Not yet approved or drilled)	CASTLEGATE	CARBON	12S-10E	17	12	S	10	E	NENW
43-007-30768-00-00	EVERGREEN OPERATING CORP	HUBER-JENSEN 1-8	Gas Well	Producing	CASTLEGATE	CARBON	12S-10E	8	12	S	10	E	NESE
43-007-30769-00-00	EVERGREEN OPERATING CORP	HUBER-JENSEN 1-17	Gas Well	New Permit (Not yet approved or drilled)	CASTLEGATE	CARBON	12S-10E	17	12	S	10	E	NENE
43-007-30783-00-00	EVERGREEN OPERATING CORP	HUBER-ST 2-16	Gas Well	Approved permit (APD); not yet spudded	CASTLEGATE	CARBON	12S-10E	16	12	S	10	E	NWSE
43-007-30784-00-00	EVERGREEN OPERATING CORP	HUBER-ST 3-16	Gas Well	Approved permit (APD); not yet spudded	CASTLEGATE	CARBON	12S-10E	16	12	S	10	E	SESW
43-007-30785-00-00	EVERGREEN OPERATING CORP	HUBER-ST 4-16	Gas Well	Producing	CASTLEGATE	CARBON	12S-10E	16	12	S	10	E	SE
43-007-30787-00-00	EVERGREEN OPERATING CORP	H-M FED 2-14	Gas Well	New Permit (Not yet approved or drilled)	CASTLEGATE	CARBON	12S-10E	14	12	S	10	E	NES
43-007-30810-00-00	EVERGREEN OPERATING CORP	HUBER-JENSEN 2-5	Gas Well	New Permit (Not yet approved or drilled)	CASTLEGATE	CARBON	12S-10E	5	12	S	10	E	NESW
43-007-30858-00-00	EVERGREEN OPERATING CORP	HUBER-JENSEN 4-17	Gas Well	New Permit (Not yet approved or drilled)	CASTLEGATE	CARBON	12S-10E	17	12	S	10	E	NESE
43-007-30859-00-00	EVERGREEN OPERATING CORP	HUBER-JENSEN 2-18	Gas Well	New Permit (Not yet approved or drilled)	CASTLEGATE	CARBON	12S-10E	18	12	S	10	E	NENE
43-007-30860-00-00	EVERGREEN OPERATING CORP	HUBER-JENSEN 4-8	Gas Well	New Permit (Not yet approved or drilled)	CASTLEGATE	CARBON	12S-10E	8	12	S	10	E	NWSW

**EVERGREEN TO PIONEER NATURAL RESOURCES USA, INC. MERGER**  
**WELL LIST 10/15/04**

API Well Number	Operator	Well Name	Well Type	Well Status	Field Name	County Name	Location (Twn-Rng)	Sect	TrpN	TrpE	RngW	RngE	Qtr/Qtr
43-007-30947-00-00	EVERGREEN OPERATING CORP	HUBER-FRANDSEN/FED 4-15	Gas Well	New Permit (Not yet approved or drilled)	CASTLEGATE	CARBON	12S-10E	15	12	S	10	E	NWNW
43-007-30961-00-00	EVERGREEN OPERATING CORP	STATE 11-16	Gas Well	Spudded (Drilling commenced: Not yet completed)	CASTLEGATE	CARBON	12S-10E	16	12	S	10	E	NWNW
43-007-30962-00-00	EVERGREEN OPERATING CORP	SHIMMIN 11-14	Gas Well	Spudded (Drilling commenced: Not yet completed)	CASTLEGATE	CARBON	12S-10E	14	12	S	10	E	NWNW
43-007-30788	EVERGREEN OPERATING CORP	Jensen 7-15 Deep	Gas Well	Active	WILDCAT	CARBON	12S-10E	15	12	S	10	E	SWNE
43-007-30977-00-00	EVERGREEN OPERATING CORP	JENSEN 24-4	Gas Well	New Permit (Not yet approved or drilled)	CASTLEGATE	CARBON	12S-10E	4	12	S	10	E	SESW
43-007-30978-00-00	EVERGREEN OPERATING CORP	JENSEN 34-5	Gas Well	New Permit (Not yet approved or drilled)	CASTLEGATE	CARBON	12S-10E	5	12	S	10	E	SWSE
43-007-30980-00-00	EVERGREEN OPERATING CORP	JENSEN 41-9	Gas Well	New Permit (Not yet approved or drilled)	CASTLEGATE	CARBON	12S-10E	9	12	S	10	E	NENE
43-007-30981-00-00	EVERGREEN OPERATING CORP	JENSEN 34-10	Gas Well	New Permit (Not yet approved or drilled)	CASTLEGATE	CARBON	12S-10E	10	12	S	10	E	SWSE
43-013-32308-00-00	EVERGREEN OPERATING CORP	HUBER-ST 1-35	Water Disposal Well	Active	CASTLEGATE	DUCHESNE	11S-10E	35	11	S	10	E	SW
43-013-32317-00-00	EVERGREEN OPERATING CORP	HUBER-STATE 1-27	Gas Well	New Permit (Not yet approved or drilled)	WILDCAT	DUCHESNE	11S-10E	27	11	S	10	E	SWSE
43-017-30494-00-00	EVERGREEN OIL CORP	POISON SPRINGS U 1 USA	Oil Well	Plugged and Abandoned	WILDCAT	GARFIELD	04S-12E	24	04	S	12	E	NESE
43-017-30102-00-00	EVERGREEN OIL CORP	POISON SPRINGS U 2 USA	Oil Well	Plugged and Abandoned	WILDCAT	GARFIELD	04S-12E	04	04	S	12	E	NENE
43-019-30136-00-00	EVERGREEN OPERATING CORP	ANDERSON FED 2	Gas Well	Producing	EAST CANYON	GRAND	16S-24E	12	16	S	24	E	SWSW
43-019-30955-00-00	EVERGREEN OPERATING CORP	FEDERAL 24-1	Gas Well	Shut-In	EAST CANYON	GRAND	16S-24E	24	16	S	24	E	NWNE
43-019-31077-00-00	EVERGREEN OPERATING CORP	FEDERAL 1-34	Gas Well	Producing	BRYSON CANYON	GRAND	16S-24E	34	16	S	24	E	NESE
43-019-31078-00-00	EVERGREEN OPERATING CORP	FEDERAL 2-34	Gas Well	Producing	BRYSON CANYON	GRAND	16S-24E	34	16	S	24	E	SESW
43-047-30248-00-00	EVERGREEN OPERATING CORP	BLACK HORSE 2	Gas Well	Shut-In	BLACK HORSE CYN	UINTAH	15S-24E	29	15	S	24	E	SESE
43-047-30284-00-00	EVERGREEN OPERATING CORP	PINE SPRING U 1	Gas Well	Producing	PINE SPRINGS	UINTAH	14S-22E	15	14	S	22	E	NESW
43-047-30325-00-00	EVERGREEN OPERATING CORP	RAT HOLE CYN 1	Gas Well	Shut-In	RAT HOLE CANYON	UINTAH	14S-25E	8	14	S	25	E	NWSE
43-047-30331-00-00	EVERGREEN OPERATING CORP	DRY BURN U 1	Gas Well	Shut-In	DRY BURN	UINTAH	13S-25E	29	13	S	25	E	NWSE
43-047-30332-00-00	EVERGREEN OPERATING CORP	1-L-23	Gas Well	Shut-In	SWEETWATER CYN	UINTAH	14S-24E	23	14	S	24	E	SWNE
43-047-30460-00-00	EVERGREEN OPERATING CORP	SWEETWATER CYN 1	Gas Well	Shut-In	SWEETWATER CYN	UINTAH	14S-24E	14	14	S	24	E	SWNW
43-047-30582-00-00	EVERGREEN OPERATING CORP	TRAPP SPRINGS 4-25-14-23	Gas Well	Producing	MAIN CANYON	UINTAH	14S-23E	25	14	S	23	E	SWSW
43-047-30619-00-00	EVERGREEN OPERATING CORP	CROOKED CYN 13-17-14-23	Gas Well	Producing	CROOKED CANYON	UINTAH	14S-23E	17	14	S	23	E	NWNW
43-047-30622-00-00	EVERGREEN OPERATING CORP	WOLF UNIT 3-11-15-21	Gas Well	Shut-In	WOLF POINT	UINTAH	15S-21E	11	15	S	21	E	SESW
43-047-30639-00-00	EVERGREEN OPERATING CORP	MAIN CYN 11-10-15-23	Gas Well	Producing	MAIN CANYON	UINTAH	15S-23E	10	15	S	23	E	SESW
43-047-30674-00-00	EVERGREEN OPERATING CORP	MAIN CYN 15-8-15-23	Gas Well	Producing	MAIN CANYON	UINTAH	15S-23E	8	15	S	23	E	NWNE
43-047-30735-00-00	EVERGREEN OPERATING CORP	MAIN CYN 2-8-15-23	Gas Well	Producing	MAIN CANYON	UINTAH	15S-23E	8	15	S	23	E	SWSE
43-047-30736-00-00	EVERGREEN OPERATING CORP	MAIN CYN 7-17-15-23	Gas Well	Producing	MAIN CANYON	UINTAH	15S-23E	17	15	S	23	E	NWSE
43-047-30746-00-00	EVERGREEN OPERATING CORP	STATE 11-2-15-22	Gas Well	Plugged and Abandoned	MAIN CANYON	UINTAH	15S-22E	2	15	S	22	E	SESW
43-047-30791-00-00	EVERGREEN OPERATING CORP	TRAPP SPRINGS 6-35-14-23	Gas Well	Producing	MAIN CANYON	UINTAH	14S-23E	35	14	S	23	E	NESE
43-047-30844-00-00	EVERGREEN OPERATING CORP	TRAPP SPRINGS 8-36-14-23	Gas Well	Producing	MAIN CANYON	UINTAH	14S-23E	36	14	S	23	E	NESE
43-047-30975-00-00	EVERGREEN OPERATING CORP	TRAPP SPRINGS 1-25-14-23	Gas Well	Producing	MAIN CANYON	UINTAH	14S-23E	25	14	S	23	E	SESE
43-047-30977-00-00	EVERGREEN OPERATING CORP	MAIN CYN 8-7-15-23	Gas Well	Producing	MAIN CANYON	UINTAH	15S-23E	7	15	S	23	E	NESE
43-047-31003-00-00	EVERGREEN OPERATING CORP	TRAPP SPRINGS 3-26-14-23	Gas Well	Shut-In	MAIN CANYON	UINTAH	14S-23E	26	14	S	23	E	SESW
43-047-31027-00-00	EVERGREEN OPERATING CORP	FEDERAL 6-14-15-21	Gas Well	Shut-In	WOLF POINT	UINTAH	15S-21E	14	15	S	21	E	NESW
43-047-31040-00-00	EVERGREEN OPERATING CORP	SWEETWATER 6-13-14-24	Gas Well	Shut-In	SWEETWATER CYN	UINTAH	14S-24E	13	14	S	24	E	NESW
43-047-31041-00-00	EVERGREEN OPERATING CORP	TRAPP SPRINGS 16-25-14-23	Gas Well	Producing	MAIN CANYON	UINTAH	14S-23E	25	14	S	23	E	NENE
43-047-31042-00-00	EVERGREEN OPERATING CORP	PINE SPRINGS 7-21-14-22	Gas Well	Producing	PINE SPRINGS	UINTAH	14S-22E	21	14	S	22	E	NWSE
43-047-31043-00-00	EVERGREEN OPERATING CORP	MAIN CYN 4-4-15-23	Gas Well	Producing	MAIN CANYON	UINTAH	15S-23E	4	15	S	23	E	SWSW
43-047-31045-00-00	EVERGREEN OPERATING CORP	BLACK HORSE 14-15-15-24	Gas Well	Shut-In	SOUTH CANYON	UINTAH	15S-24E	15	15	S	24	E	NENW
43-047-31063-00-00	EVERGREEN OPERATING CORP	PINE SPRINGS 8-20-14-22	Gas Well	Producing	PINE SPRINGS	UINTAH	14S-22E	20	14	S	22	E	NESE

**EVERGREEN TO PIONEER NATURAL RESOURCES USA, INC. MERGER**  
**WELL LIST 10/15/04**

API Well Number	Operator	Well Name	Well Type	Well Status	Field Name	County Name	Location (Twn-Rng)	Sect	Twpr	Twpr	RngN	RngD	Qtr/Qtr
43-047-31071-00-00	EVERGREEN OPERATING CORP	FEDERAL 7-15-15-21	Gas Well	Shut-In	WOLF POINT	UINTAH	15S-21E	15	15	S	21	E	NWSE
43-047-31072-00-00	EVERGREEN OPERATING CORP	MAIN CYN 6-3-15-23	Gas Well	Shut-In	MAIN CANYON	UINTAH	15S-23E	3	15	S	23	E	NESW
43-047-31073-00-00	EVERGREEN OPERATING CORP	MAIN CYN 6-8-15-23	Gas Well	Producing	MAIN CANYON	UINTAH	15S-23E	8	15	S	23	E	NESW
43-047-31074-00-00	EVERGREEN OPERATING CORP	PINE SPRINGS 13-26-14-22	Gas Well	Producing	PINE SPRINGS	UINTAH	14S-22E	26	14	S	22	E	NWNW
43-047-31091-00-00	EVERGREEN OPERATING CORP	FEDERAL 2-18-15-22	Gas Well	Shut-In	WOLF POINT	UINTAH	15S-22E	18	15	S	22	E	SWSE
43-047-31096-00-00	EVERGREEN OPERATING CORP	PINE SPRINGS 9-12-14-21	Gas Well	Producing	PINE SPRINGS	UINTAH	14S-21E	12	14	S	21	E	SENE
43-047-31104-00-00	EVERGREEN OPERATING CORP	BLACK HORSE 12-8-15-24	Gas Well	Shut-In	SOUTH CANYON	UINTAH	15S-24E	8	15	S	24	E	SWNW
43-047-31111-00-00	EVERGREEN OPERATING CORP	MAIN CYN 16-4-15-23	Gas Well	Shut-In	MAIN CANYON	UINTAH	15S-23E	4	15	S	23	E	NENE
43-047-31134-00-00	EVERGREEN OPERATING CORP	FED ENI 7-1	Gas Well	Producing	DAVIS CANYON	UINTAH	13S-26E	7	13	S	26	E	NENE
43-047-31135-00-00	EVERGREEN OPERATING CORP	STATE 8-2-15-22	Gas Well	Shut-In	MAIN CANYON	UINTAH	15S-22E	2	15	S	22	E	NESE
43-047-31137-00-00	EVERGREEN OPERATING CORP	FEDERAL 5-13-15-21	Gas Well	Shut-In	WOLF POINT	UINTAH	15S-21E	13	15	S	21	E	NWSW
43-047-31348-00-00	EVERGREEN OPERATING CORP	FEDERAL 12-18-14-22	Gas Well	Shut-In	PINE SPRINGS	UINTAH	14S-22E	18	14	S	22	E	SWNW
43-047-34674-00-00	EVERGREEN OPERATING CORP	PINE SPRINGS FED 9-23-14S-22E	Gas Well	Location Abandoned	PINE SPRINGS	UINTAH	14S-22E	23	14	S	22	E	SENE
43-047-34675-00-00	EVERGREEN OPERATING CORP	PINE SPRINGS FED 3-23-14S-22E	Gas Well	Producing	PINE SPRINGS	UINTAH	14S-22E	23	14	S	22	E	SESW
43-047-34676-00-00	EVERGREEN OPERATING CORP	PINE SPRINGS FED 12-23-14S-22E	Gas Well	Temporarily Abandoned	PINE SPRINGS	UINTAH	14S-22E	23	14	S	22	E	SWNW
43-047-34941-00-00	EVERGREEN OPERATING CORP	BONANZA FED 15-27-10-25	Gas Well	Producing	UNDESIGNATED	UINTAH	10S-25E	27	10	S	25	E	NWNE
43-047-35555-00-00	EVERGREEN OPERATING CORP	PINE SPRINGS ST 6-36-14-22	Gas Well	Spudded (Drilling commenced. Not yet completed)	UNDESIGNATED	UINTAH	14S-22E	36	14	S	22	E	NE
43-047-35556-00-00	EVERGREEN OPERATING CORP	PINE SPRINGS FED 4-22-14-22	Gas Well	Approved permit (APD); not yet spudded	PINE SPRINGS	UINTAH	14S-22E	22	14	S	22	E	SWSW
43-047-35566-00-00	EVERGREEN OPERATING CORP	PINE SPRINGS FED 15-21-14-22	Gas Well	Approved permit (APD); not yet spudded	PINE SPRINGS	UINTAH	14S-22E	21	14	S	22	E	NWNE

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

**SUNDRY NOTICES AND REPORTS ON WELLS**

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER:
2. NAME OF OPERATOR: Pioneer Natural Resources		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: 1401 17th St., Suite 1200 CITY Denver STATE CO ZIP 80202		7. UNIT or CA AGREEMENT NAME:
4. LOCATION OF WELL FOOTAGES AT SURFACE: COUNTY: QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: STATE: UTAH		8. WELL NAME and NUMBER: See attached list
PHONE NUMBER: (303) 298-8100		9. API NUMBER: 43-007-30735
10. FIELD AND POOL, OR WILDCAT:		

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: 1/13/2006	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion:	<input checked="" type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Change well name from "State Well Name" (Column 1) to "Well Name" (Column 2). See attached list for wells.

NAME (PLEASE PRINT) Kallasandra M. Boulay	TITLE Engineering Analyst
SIGNATURE 	DATE 1/3/2006

(This space for State use only)

RECEIVED

JAN 06 2006

DIV. OF OIL, GAS & MINING

Pioneer Natural Resources  
1401 17th Street, Suite 1200  
Denver, Colorado 80202  
Contact: Kallasandra Boulay  
Phone: (303) 675-2719

RECEIVED  
JAN 06 2006  
DIV. OF OIL, GAS & MINING

State Well Name	Well Name	Q	S	T	R	State	County	Field	Status (State)	API #	Operator	Well Type
✓ Huber-Federal 7-9	Huber Federal 7-9-12-10	SWNE	9	12S	10E	Utah	Carbon	Castlegate	PR	43-007-30137	PNR	Gas Well
✓ Huber-Jensen 1-10	Huber Jensen 1-10-12-10	NWSW	10	12S	10E	Utah	Carbon	Castlegate	PR	43-007-30596	PNR	Gas Well
✓ Huber-Jensen 11-10	Huber Jensen 11-10-12-10	NESW	10	12S	10E	Utah	Carbon	Castlegate	PR	43-007-30164	PNR	Gas Well
✓ Huber-Jensen 1-15	Huber Jensen 1-15-12-10	SWNE	15	12S	10E	Utah	Carbon	Castlegate	PR	43-007-30736	PNR	Gas Well
✓ Huber-Jensen 1-4	Huber Jensen 1-4-12-10	SWSE	4	12S	10E	Utah	Carbon	Castlegate	PR	43-007-30733	PNR	Gas Well
✓ Huber-Jensen 16-9	Huber Jensen 16-9-12-10	SESE	9	12S	10E	Utah	Carbon	Castlegate	PR	43-007-30163	PNR	Gas Well
✓ Huber-Jensen 1-8	Huber Jensen 1-8-12-10	NESE	8	12S	10E	Utah	Carbon	Castlegate	PR	43-007-30768	PNR	Gas Well
✓ Huber-Jensen 1-9	Huber Jensen 1-9-12-10	NWSW	9	12S	10E	Utah	Carbon	Castlegate	PR	43-007-30717	PNR	Gas Well
✓ Huber-Jensen 2-8	Huber Jensen 2-8-12-10	NENE	8	12S	10E	Utah	Carbon	Castlegate	PR	43-007-30734	PNR	Gas Well
✓ Huber-Jensen 2-9	Huber Jensen 2-9-12-10	NENW	9	12S	10E	Utah	Carbon	Castlegate	PR	43-007-30735	PNR	Gas Well
✓ Huber-Jensen 5-10	Huber Jensen 5-10-12-10	SWNW	10	12S	10E	Utah	Carbon	Castlegate	PR	43-007-30162	PNR	Gas Well
✓ Huber-Jensen 9-10	Huber Jensen 9-10-12-10	NESE	10	12S	10E	Utah	Carbon	Castlegate	PR	43-007-30159	PNR	Gas Well
✓ Huber-Shimmin Trust 1-11	Huber Shimmin Trust 1-11-12-10	SWSW	11	12S	10E	Utah	Carbon	Castlegate	PR	43-007-30673	PNR	Gas Well
✓ Huber-Shimmin Trust 1-12	Huber Shimmin Trust 1-12-12-10	NWSW	12	12S	10E	Utah	Carbon	Castlegate	PR	43-007-30674	PNR	Gas Well
✓ Huber-Shimmin Trust 2-11	Huber Shimmin Trust 2-11-12-10	SESE	11	12S	10E	Utah	Carbon	Castlegate	PR	43-007-30659	PNR	Gas Well
✓ Huber-Shimmin Trust 3-14	Huber Shimmin Trust 3-14-12-10	SENE	14	12S	10E	Utah	Carbon	Castlegate	SI	43-007-30640	PNR	Gas Well
✓ Huber-Shimmin Trust 4-14	Huber Shimmin Trust 4-14-12-10	SENE	14	12S	10E	Utah	Carbon	Castlegate	PR	43-007-30662	PNR	Gas Well
✓ Huber-State 1-16	Huber State 1-16-12-10	NWNE	16	12S	10E	Utah	Carbon	Castlegate	PR	43-007-30589	PNR	Gas Well
✓ Huber -St 4-16	Huber State 4-16-12-10	SENE	16	12S	10E	Utah	Carbon	Castlegate	PR	43-007-30785	PNR	Gas Well
✓ Jensen 7-15 Deep	Jensen Deep 7-15-12-10	SWNE	15	12S	10E	Utah	Carbon	Castlegate	TA	43-007-30786	PNR	Gas Well
✓ Shimmin Trust 11-11	Shimmin Trust 11-11-12-10	NESW	11	12S	10E	Utah	Carbon	Castlegate	PR	43-007-30166	PNR	Gas Well
✓ Shimmin Trust 14-12	Shimmin Trust 14-12-12-10	SESW	12	12S	10E	Utah	Carbon	Castlegate	XX	43-007-30169	PNR	Gas Well
✓ Shimmin Trust 5	Shimmin Trust 5-14-12-10	NWNE	14	12S	10E	Utah	Carbon	Castlegate	PR	43-007-30122	PNR	Gas Well
✓ Huber-St 1-35	Huber State 1-35-12-10 WDW	SWSW	35	12S	10E	Utah	Duchesne	Castlegate	Active	43-013-32308	PNR	WDW
✓ Anderson Fed 2	Anderson Federal 2-12-16S-24E	SWSW	12	16S	24E	Utah	Grand	East Canyon	PR	43-019-30136	PNR	Gas Well
✓ Federal 1-34	Bryson Canyon Federal 1-34-16S-24E	NESE	34	16S	24E	Utah	Grand	Bryson Canyon	PR	43-019-31077	PNR	Gas Well
✓ Federal 2-34	Bryson Canyon Federal 2-34-16S-24E	SESW	34	16S	24E	Utah	Grand	Bryson Canyon	PR	43-019-31078	PNR	Gas Well
✓ Federal 24-1	East Canyon Federal 24-1-16S-24E	NWNE	1	16S	24E	Utah	Grand	East Canyon	PA	43-019-30955	PNR	Gas Well
✓ Black Horse 2	Black Horse 2 1-29-15S-24E	SESE	29	15S	24E	Utah	Uintah	Black Horse Canyon	SI	43-047-30248	PNR	Gas Well
✓ Fed ENI 7-1	Davis Canyon Federal ENI 7-1-13S-26E	NENE	1	13S	26E	Utah	Uintah	Davis Canyon	SI	43-047-31134	PNR	Gas Well



**STATE OF UTAH**  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

**SUNDRY NOTICES AND REPORTS ON WELLS**

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: <b>Fee</b>
2. NAME OF OPERATOR: <b>Pioneer Natural Resources</b>		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: 1401 17th St., Suite 1200 CITY <b>Denver</b> STATE <b>CO</b> ZIP <b>80202</b>		7. UNIT or CA AGREEMENT NAME:
4. LOCATION OF WELL FOOTAGES AT SURFACE: <b>330' FNL &amp; 1520' FWL</b>  QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: <b>NENW 9 12S 10E</b>		8. WELL NAME and NUMBER: <b>Huber Jensen 2-9-12-10</b> 9. API NUMBER: <b>4300730735</b> 10. FIELD AND POOL, OR WILDCAT: <b>Castlegate</b>
		COUNTY: <b>Carbon</b>  STATE: <b>UTAH</b>


11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate)  Approximate date work will start:  _____	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> DEEPEN <input checked="" type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> PLUG BACK <input type="checkbox"/> PRODUCTION (START/RESUME) <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	<input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> TEMPORARILY ABANDON <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> WATER SHUT-OFF <input type="checkbox"/> OTHER: _____

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Pioneer Natural Resources (formerly Evergreen Operating Corp. and operator at time of work) fracture treated this well.

From 6/22/2004 to 6/29/2004 well was frac'd in 8 stages from 4624'-5030' with 188 total shots.

Pumped combination of XL Fluid / Sand and 70% foam frac fluids with 1,770 total bbls water, 14,300 SCF Nitrogen and 64,000 lbs. sand.

NAME (PLEASE PRINT) <u>Kallasandra M. Boulay</u>	TITLE <u>Engineering Analyst</u>
SIGNATURE 	DATE <u>1/31/2006</u>

(This space for State use only)

FEB 06 2006

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____	5. LEASE DESIGNATION AND SERIAL NUMBER: FEE
2. NAME OF OPERATOR: Pioneer Natural Resources USA, Inc., Attn: Kally Moran	6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: 1401 17th Street, # 1200 CITY Denver STATE CO ZIP 80202	7. UNIT or CA AGREEMENT NAME:
PHONE NUMBER: (303) 675-2719	8. WELL NAME and NUMBER: Huber Jensen 2-9-12-10
10. FIELD AND POOL, OR WILDCAT: Castlegate	9. API NUMBER: 4300730735

4. LOCATION OF WELL FOOTAGES AT SURFACE: 330 FNL 1520 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NENW 9 12S 10E	COUNTY: Carbon STATE: UTAH
---	-------------------------------

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> DEEPEN <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> PLUG BACK <input type="checkbox"/> PRODUCTION (START/RESUME) <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	<input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> TEMPORARILY ABANDON <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> WATER SHUT-OFF <input checked="" type="checkbox"/> OTHER: Daily Workover Report
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: 9/26/2006			


12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Please be advised that Pioneer Natural Resources has completed the following work on the Huber Jensen 2-9-12-10.

Primary Job: Pump Change  
Secondary Job: Replace Rods  
Start Date: 9/19/2006  
End Date: 9/26/2006

9/19/2006 - MIRU

9/20/2006 - Blow down well, RU rig equip to tbq, load w/ 2 bbls water. Test to 500# and held. Unseat pump, lay down polish rod and ponys. 1 8' x 1" and 2 6' x 1". POOH, laying down w/ 61 1" rods, stand back 65 7/8" rods, lay down remaining 67 7/8" rods, 8 1: rods, and pump. RD floor and rod equip. Change over to tbq equip. ND wellhead, release TAC, NU BOP's. POOH w/ 145 jts 2-7/8" tbq. Tac, 12 jts 2-7/8" tbq, SN perf sub, 1 jt 2-7/8" tbq and NC. PU 4-3/4" but and 5-1/2" csg scrapper, x-over. RIH and tally w/ 38 jts 2-7/8" tbq.

NAME (PLEASE PRINT) Kallassandra M. Moran	TITLE Engineering Analyst
SIGNATURE 	DATE 10/17/2006

(This space for State use only)

RECEIVED  
OCT 20 2006

- 9/21/2006 - Finish RIH and tally w/ 120 jts 2-7/8" tbg. PU 1 jt 2-7/8" tbg to tag at 5138'. POOH w/ 159 jts 2-7/8" tbg, 5-1/2" csg scraper, and 4-3/4" bit. PU NC, flapper, 2' pup, flapper, 16 jts 2-7/8" tbg, bailer, flapper, 4' pup, drain, and 142 jts 2-7/8" tbg. Tagged fill at 5138', cleaned out to 5161'. Tagged solid, POOH w/ 158 jts 2-7/8" tbg. Lay down bailer and flappers.
- 9/22/2006 - PU packer, SN and RIH w/ 132 jts 2-7/8" tbg. Set packer at 4279', load w/ 65 bbls water, test packer to 500# (held). Drain pump and circ equip.
- 9/25/2006 - RU Halliburton pump, pump acid job, RD Halliburton, RU swab equip, tagged fluid at 3600'. RD swab equip, release packer, and POOH w/ 132 jts 2-7/8" tbg, SN, packer. RIH w/ NC, 1 jt 2-7/8" tbg, SN, 15 jts 2-7/8" tbg, TAC, 142 jts 2-7/8" tbg. RD floor and equip, ND BOP's. Set TAC w/ 10 pts tension, land tbg at 5135'. NU wellhead.
- 9/26/2006 - Blow down well. RU floor and change from tbg to rod pump equip. PU and test pump, PU and install rod guides on 6 1" rods, 132 3/4" rods, RIH w/ 64 7/8" rods. Installing rod guides. PUI 1 6' x 7/8" pony and polish rod. Space out pump and seat. RU pumping unit, load tbg w/ 25 bbls of water. Well pumped up. RD rid and equip.

*Kum*

Division of Oil, Gas and Mining  
**OPERATOR CHANGE WORKSHEET (for state use only)**

**ROUTING**

1. DJJ

2. CDW

**X - Change of Operator (Well Sold)**

Operator Name Change/Merger

The operator of the well(s) listed below has changed, effective:

**4/1/2010**

**FROM: (Old Operator):**

N5155-Pioneer Natural Resources USA, Inc.  
 1401 17th St, Suite 1200  
 Denver, CO 80202

Phone: 1 (303) 675-2610

**TO: ( New Operator):**

N3680-Blue Tip Castlegate, Inc.  
 15810 Park Ten Place, Suite 160  
 Houston, TX 77084

Phone: 1 (303) 979-6023

**CA No.**

**Unit:**

WELL NAME	SEC	TWN	RNG	API NO	ENTITY NO	LEASE TYPE	WELL TYPE	WELL STATUS
SEE ATTACHED LIST								

**OPERATOR CHANGES DOCUMENTATION**

Enter date after each listed item is completed

- (R649-8-10) Sundry or legal documentation was received from the **FORMER** operator on: 6/3/2010
- (R649-8-10) Sundry or legal documentation was received from the **NEW** operator on: 6/3/2010
- The new company was checked on the **Department of Commerce, Division of Corporations Database** on: 5/10/2010
- a. Is the new operator registered in the State of Utah: Business Number: 7624076-0142
- a. (R649-9-2)Waste Management Plan has been received on: Requested 9/13/2010
- b. Inspections of LA PA state/fee well sites complete on: n/a
- c. Reports current for Production/Disposition & Sundries on: ok
- Federal and Indian Lease Wells:** The BLM and or the BIA has approved the merger, name change, or operator change for all wells listed on Federal or Indian leases on: BLM not yet BIA
- Federal and Indian Units:**  
The BLM or BIA has approved the successor of unit operator for wells listed on: n/a
- Federal and Indian Communization Agreements ("CA"):**  
The BLM or BIA has approved the operator for all wells listed within a CA on: n/a
- Underground Injection Control ("UIC")** Division has approved UIC Form 5 Transfer of Authority to **Inject**, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on: \* Being held

**DATA ENTRY:**

- Changes entered in the **Oil and Gas Database** on: 6/30/2010
- Changes have been entered on the **Monthly Operator Change Spread Sheet** on: 6/30/2010
- Bond information entered in RBDMS on: 6/30/2010
- Fee/State wells attached to bond in RBDMS on: 6/30/2010
- Injection Projects to new operator in RBDMS on: \*
- Receipt of Acceptance of Drilling Procedures for APD/New on: 6/30/2010

**BOND VERIFICATION:**

- Federal well(s) covered by Bond Number: B005638
- Indian well(s) covered by Bond Number: n/a
- a. (R649-3-1) The **NEW** operator of any state/fee well(s) listed covered by Bond Number B005639 and B005650
- b. The **FORMER** operator has requested a release of liability from their bond on: n/a

**LEASE INTEREST OWNER NOTIFICATION:**

- (R649-2-10) The **NEW** operator of the fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: 6/30/2010

**COMMENTS:**

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER:
2. NAME OF OPERATOR: Blue Tip Castlegate, Inc. <i>N 36 80</i>		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: 15810 Park Ten Place - Ste 160 CITY Houston STATE TX ZIP 77084		7. UNIT or CA AGREEMENT NAME:
PHONE NUMBER: (303) 979-6023		8. WELL NAME and NUMBER: See Attached List
4. LOCATION OF WELL FOOTAGES AT SURFACE: COUNTY: Carbon		9. API NUMBER:
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: STATE: UTAH		10. FIELD AND POOL, OR WILDCAT:

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: <u>4/1/2010</u>	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion:	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input checked="" type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Blue Tip Castlegate, Inc. has acquired all of Pioneer Natural Resources USA, Inc's interest in the Castlegate Field - see attached well list. The effective date of change of operator is April 1, 2010.

*Betty Brown* 5/13/10  
Betty Brown Date  
Attorney-In-Fact  
Pioneer Natural Resources USA, Inc. *N 5155*  
1401 17th Street - Suite 1200  
Denver, CO 80202  
Phone: 303-675-2610

*Bruce L Taylor* 5/13/10  
Bruce L. Taylor Date  
Manager Vice President *BT*  
Blue Tip Castlegate, Inc.  
15810 Park Ten Place - Suite 160  
Houston, TX 77084  
Telephone: 303-979-6023  
State Bond No.: B005639  
BLM Bond No.: B005638

NAME (PLEASE PRINT) Bruce L. Taylor TITLE Manager Vice President  
SIGNATURE *Bruce L Taylor* DATE 5/13/10

(This space for State use only)

APPROVED 6/30/2010

*Earlene Russell*

(5/2000)

Division of Oil, Gas and Mining  
Earlene Russell, Engineering Technician

(See Instructions on Reverse Side)

RECEIVED

JUN 03 2010

DIV. OF OIL, GAS & MINING

PIONEER NATURAL RESOURCES (N5155) to BLUE TIP CASTLEGATE (N3680)

well_name	sec	tpw	rng	api	entity	lease	type	stat	C
SHIMMIN TRUST 5-14-12-10	14	120S	100E	4300730122	14175	Fee	GW	P	
CASTLEGATE FED 7-9-12-10	09	120S	100E	4300730137	12991	Federal	GW	P	
JENSEN 9-10-12-10	10	120S	100E	4300730159	12906	Fee	GW	P	
JENSEN 5-10-12-10	10	120S	100E	4300730162	12905	Fee	GW	S	
JENSEN 16-9-12-10	09	120S	100E	4300730163	12904	Fee	GW	P	
JENSEN 11-10-12-10	10	120S	100E	4300730164	11405	Fee	GW	P	
SHIMMIN TRUST 11-11-12-10	11	120S	100E	4300730166	11410	Fee	GW	P	
CASTLEGATE ST 1-16-12-10	16	120S	100E	4300730589	12610	State	GW	P	
JENSEN 1-10-12-10	10	120S	100E	4300730596	12611	Fee	GW	P	
SHIMMIN TRUST 2-11-12-10	11	120S	100E	4300730659	13070	Fee	GW	P	
SHIMMIN TRUST 4-14-12-10	14	120S	100E	4300730662	13071	Fee	GW	P	
SHIMMIN TRUST 1-11-12-10	11	120S	100E	4300730673	12901	Fee	GW	P	
JENSEN 2-10-12-10	10	120S	100E	4300730675	14225	Fee	GW	OPS	
JENSEN 1-9-12-10	09	120S	100E	4300730717	12903	Fee	GW	P	
JENSEN 1-18-12-10	18	120S	100E	4300730718	14226	Fee	GW	P	
JENSEN 1-4-12-10	04	120S	100E	4300730733	13068	Fee	GW	P	
JENSEN 2-8-12-10	08	120S	100E	4300730734	13275	Fee	GW	P	
JENSEN 2-9-12-10	09	120S	100E	4300730735	13317	Fee	GW	P	
JENSEN 1-15-12-10	15	120S	100E	4300730736	13072	Fee	GW	P	
JENSEN 1-8-12-10	08	120S	100E	4300730768	13359	Fee	GW	P	
CASTLEGATE ST 4-16-12-10	16	120S	100E	4300730785	13318	State	GW	P	
JENSEN DEEP 7-15-12-10	15	120S	100E	4300730786	13247	Fee	GW	S	
CASTLEGATE ST 11-16H-12-10	16	120S	100E	4300730961	14224	State	GW	S	
SHIMMIN 11-14-12-10	14	120S	100E	4300730962	14223	Fee	GW	OPS	
JENSEN 23C-9-12-10	09	120S	100E	4300731211	15770	Fee	GW	P	
JENSEN 33C-9-12-10	09	120S	100E	4300731212	15769	Fee	GW	P	
JENSEN 42C-9-12-10	09	120S	100E	4300731213	15766	Fee	GW	P	
JENSEN 43C-9-12-10	09	120S	100E	4300731214	15768	Fee	GW	P	C
CASTLEGATE FED 22C-9-12-10	09	120S	100E	4300731225	15767	Federal	GW	P	
JENSEN 41C-9-12-10	09	120S	100E	4300731452	17246	Fee	GW	OPS	C
JENSEN 14C-10-12-10	10	120S	100E	4300731453	17235	Fee	GW	P	
JENSEN FED 14C-3-12-10	03	120S	100E	4300731495		Federal	GW	APD	C
JENSEN FED 22C-10-12-10	10	120S	100E	4300731498		Federal	GW	APD	C
JENSEN FED 11C-10-12-10	10	120S	100E	4300731499		Federal	GW	APD	C
JENSEN 14C-4-12-10	04	120S	100E	4300731500		Fee	GW	APD	C
JENSEN 44C-4-12-10	04	120S	100E	4300731501		Fee	GW	APD	C
JENSEN 44C-5-12-10	05	120S	100E	4300731502		Fee	GW	APD	C
JENSEN 34C-9-12-10	09	120S	100E	4300731503		Fee	GW	APD	C
JENSEN 31C-9-12-10	09	120S	100E	4300731504		Fee	GW	APD	C
JENSEN 14C-9-12-10	09	120S	100E	4300731505		Fee	GW	APD	C
JENSEN 11C-9-12-10	09	120S	100E	4300731506		Fee	GW	APD	C
JENSEN 24C-9-12-10	09	120S	100E	4300731507		Fee	GW	APD	C
JENSEN ST 11C-34-11-9	34	110S	090E	4304930024	17071	State	GW	S	C

Division of Oil, Gas and Mining  
Operator Change/Name Change Worksheet-for State use only

Effective Date: 7/1/2016

FORMER OPERATOR:	NEW OPERATOR:
Blue Tip Castlegate, Inc. 15810 Park Ten Place, Suite 160 Houston TX 77084	Liberty Pioneer Energy Sources, Inc. 1411 East 840 North Orem UT 84097
CA Number(s):	Unit(s): N/A

**WELL INFORMATION:**

Well Name	Sec	TWN	RNG	API	Entity	Mineral	Surface	Type	Status
See Attached List									

**OPERATOR CHANGES DOCUMENTATION:**

1. Sundry or legal documentation was received from the **FORMER** operator on: 7/21/2016
2. Sundry or legal documentation was received from the **NEW** operator on: 7/21/2016
3. New operator Division of Corporations Business Number: 6353640-0143

**REVIEW:**

1. Surface Agreement Sundry from **NEW** operator on Fee Surface wells received on: N/A
2. Receipt of Acceptance of Drilling Procedures for APD on: N/A
3. Reports current for Production/Disposition & Sundries: 8/26/2016
4. OPS/SI/TA well(s) reviewed for full cost bonding: 8/26/2016
5. UIC5 on all disposal/injection/storage well(s) approved on: 8/26/2016
6. Surface Facility(s) included in operator change: N/A
7. Inspections of PA state/fee well sites complete on (only upon operators request): N/A

**NEW OPERATOR BOND VERIFICATION:**

1. Federal well(s) covered by Bond Number: ~~N/A~~ UTB000334
2. Indian well(s) covered by Bond Number: N/A
3. State/fee well(s) covered by Bond Number(s): RLB0012097

**DATA ENTRY:**

1. Well(s) update in the **OGIS** on: 8/26/2016
2. Entity Number(s) updated in **OGIS** on: 8/26/2016
3. Unit(s) operator number update in **OGIS** on: N/A
4. Surface Facilities update in **OGIS** on: N/A
5. State/Fee well(s) attached to bond(s) in **RBDMS** on: 8/26/2016
6. Surface Facilities update in **RBDMS** on: N/A

**COMMENTS:**

From: Blue Tip Castlegate, Inc.  
To: Liberty Pioneer Energy Source, Inc.  
Effective: 7/1/2016

Well Name	Sec	TWN	RNG	API Number	Entity	Mineral	Surface	Type	Status
CASTLEGATE ST 1-35-12-10 WD	35	110S	100E	4301332308	13472	State	State	WD	A
JENSEN 9-10-12-10	10	120S	100E	4300730159	12906	Fee	Fee	GW	P
JENSEN 5-10-12-10	10	120S	100E	4300730162	12905	Fee	Fee	GW	P
JENSEN 16-9-12-10	9	120S	100E	4300730163	12904	Fee	Fee	GW	P
JENSEN 11-10-12-10	10	120S	100E	4300730164	11405	Fee	Fee	GW	P
CASTLEGATE ST 1-16-12-10	16	120S	100E	4300730589	12610	State	State	GW	P
JENSEN 1-10-12-10	10	120S	100E	4300730596	12611	Fee	Fee	GW	P
JENSEN 1-9-12-10	9	120S	100E	4300730717	12903	Fee	Fee	GW	P
JENSEN 2-9-12-10	9	120S	100E	4300730735	13317	Fee	Fee	GW	P
JENSEN 1-15-12-10	15	120S	100E	4300730736	13072	Fee	Fee	GW	P
JENSEN 1-8-12-10	8	120S	100E	4300730768	13359	Fee	Fee	GW	P
JENSEN DEEP 7-15-12-10	15	120S	100E	4300730786	13247	Fee	Fee	GW	P
JENSEN 23C-9-12-10	9	120S	100E	4300731211	15770	Fee	Fee	GW	P
JENSEN 33C-9-12-10	9	120S	100E	4300731212	15769	Fee	Fee	GW	P
JENSEN 43C-9-12-10	9	120S	100E	4300731214	15768	Fee	Fee	GW	P
CASTLEGATE FED 22C-9-12-10	9	120S	100E	4300731225	15767	Federal	Federal	GW	P
JENSEN 41C-9-12-10	9	120S	100E	4300731452	17246	Fee	Fee	GW	P
JENSEN 14C-10-12-10	10	120S	100E	4300731453	17235	Fee	Fee	GW	P
JENSEN FED 6-10-12-10	10	120S	100E	4300750177	18209	Federal	Fee	GW	P
SHIMMIN TRUST 5-14-12-10	14	120S	100E	4300730122	14175	Fee	Fee	GW	S
CASTLEGATE FED 7-9-12-10	9	120S	100E	4300730137	12991	Federal	Federal	GW	S
SHIMMIN TRUST 11-11-12-10	11	120S	100E	4300730166	11410	Fee	Fee	GW	S
SHIMMIN TRUST 2-11-12-10	11	120S	100E	4300730659	13070	Fee	Fee	GW	S
SHIMMIN TRUST 4-14-12-10	14	120S	100E	4300730662	13071	Fee	Fee	GW	S
SHIMMIN TRUST 1-11-12-10	11	120S	100E	4300730673	12901	Fee	Fee	GW	S
JENSEN 1-18-12-10	18	120S	100E	4300730718	14226	Fee	Fee	GW	S
JENSEN 1-4-12-10	4	120S	100E	4300730733	13068	Fee	Fee	GW	S
JENSEN 2-8-12-10	8	120S	100E	4300730734	13275	Fee	Fee	GW	S
CASTLEGATE ST 4-16-12-10	16	120S	100E	4300730785	13318	State	State	GW	S
CASTLEGATE ST 11-16H-12-10	16	120S	100E	4300730961	14224	State	State	GW	S
JENSEN 42C-9-12-10	9	120S	100E	4300731213	15766	Fee	Fee	GW	S
JENSEN 2C-9	9	120S	100E	4300750179	18242	Fee	Fee	GW	S
JENSEN ST 11C-34-11-9	34	110S	090E	4304930024	17071	State	Fee	GW	S



STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: SEE ATTACHED LIST
2. NAME OF OPERATOR: Liberty Pioneer Energy Source, Inc.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: 1411 E 840 N CITY Orem STATE UT ZIP 84097		7. UNIT or CA AGREEMENT NAME:
PHONE NUMBER: (801)224-4771		8. WELL NAME and NUMBER: SEE ATTACHED LIST
4. LOCATION OF WELL FOOTAGES AT SURFACE: SEE ATTACHED LIST		9. API NUMBER: SEE ATTACHED LIST
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:		10. FIELD AND POOL, OR WILDCAT:
		COUNTY:
		STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

CHANGE OF OPERATOR

PREVIOUS OPERATOR:  
Blue Tip Castlegate, Inc. N3680  
15810 Park Ten Place - Suite 160  
Houston, TX 77084  
Phone (281) 994-3800

Operator Number N3680

By: Bruce L. Taylor  
Bruce L. Taylor, Vice President

NEW OPERATOR:  
Liberty Pioneer Energy Source, Inc. N2855  
1411 East 840 North  
Orem, UT 84097  
Phone (801) 224-4771

Operator Number N2855

RECEIVED

JUL 21 2016

DIV. OF OIL, GAS & MINING

Be advised that Liberty Pioneer Energy Source, Inc. is responsible under the terms and conditions of the related leases for the operations conducted upon the leased lands. Bond coverage is covered by Bond No. RLB0012097.

NAME (PLEASE PRINT) Kimball Hodges TITLE Vice President of Liberty Pioneer Energy Source, Inc.  
SIGNATURE [Signature] DATE 7/18/16

(This space for State use only)

APPROVED

AUG 26 2016

DIV. OIL GAS & MINING  
BY: Rachael Medema

ATTACHED LIST to Change of Operator Sundry Notice

BTC WELL NUMBER	WELL NAME AND NUMBER	LEGAL DESCRIPTION	OPERATOR	API	COUNTY	STATE
2080001	JENSEN 1-4-12-10	Salt Lake Meridian T12S R10E Sec 04: SWSE	BLUE TIP CASTLEGATE INC.	43-007-30733-0000	CARBON	UTAH
2080002	JENSEN 1-8-12-10	Salt Lake Meridian T12S R10E Sec 08: NESE	BLUE TIP CASTLEGATE INC.	43-007-30768-0000	CARBON	UTAH
2080003	JENSEN 2-8-12-10	Salt Lake Meridian T12S R10E Sec 08: NENE	BLUE TIP CASTLEGATE INC.	43-007-30734-0000	CARBON	UTAH
2080004	CASTLEGATE FED 22C-9-12-10	Salt Lake Meridian T12S R10E Sec 09: SENW	BLUE TIP CASTLEGATE INC.	43-007-31225-0000	CARBON	UTAH
2080005	CASTLEGATE FED 7-9-12-10	Salt Lake Meridian T12S R10E Sec 09: SWNE	BLUE TIP CASTLEGATE INC.	43-007-30137-0000	CARBON	UTAH
2080006	JENSEN 1-9-12-10	Salt Lake Meridian T12S R10E Sec 09: NWSW	BLUE TIP CASTLEGATE INC.	43-007-30717-0000	CARBON	UTAH
2080007	JENSEN 2-9-12-10	Salt Lake Meridian T12S R10E Sec 09: NENW	BLUE TIP CASTLEGATE INC.	43-007-30735-0000	CARBON	UTAH
2080008	JENSEN 16-9-12-10	Salt Lake Meridian T12S R10E Sec 09: SESE	BLUE TIP CASTLEGATE INC.	43-007-30163-0000	CARBON	UTAH
2080009	JENSEN 23C-9-12-10	Salt Lake Meridian T12S R10E Sec 09: NESW	BLUE TIP CASTLEGATE INC.	43-007-31211-0000	CARBON	UTAH
2080010	JENSEN 33C-9-12-10	Salt Lake Meridian T12S R10E Sec 09: NWSE	BLUE TIP CASTLEGATE INC.	43-007-31212-0000	CARBON	UTAH
2080011	JENSEN 42C-9-12-10	Salt Lake Meridian T12S R10E Sec 09: SENE	BLUE TIP CASTLEGATE INC.	43-007-31213-0000	CARBON	UTAH
2080012	JENSEN 43C-9-12-10	Salt Lake Meridian T12S R10E Sec 09: NESE	BLUE TIP CASTLEGATE INC.	43-007-31214-0000	CARBON	UTAH
2080013	JENSEN 1-10-12-10	Salt Lake Meridian T12S R10E Sec 10: NWSW	BLUE TIP CASTLEGATE INC.	43-007-30596-0000	CARBON	UTAH
2080014	JENSEN 5-10-12-10	Salt Lake Meridian T12S R10E Sec 10: SWNW	BLUE TIP CASTLEGATE INC.	43-007-30162-0000	CARBON	UTAH
2080015	JENSEN 11-10-12-10	Salt Lake Meridian T12S R10E Sec 10: NESW	BLUE TIP CASTLEGATE INC.	43-007-30164-0000	CARBON	UTAH

# ATTACHED LIST to Change of Operator Sundry Notice

BTC WELL NUMBER	WELL NAME AND NUMBER	LEGAL DESCRIPTION	OPERATOR	API	COUNTY	STATE
2080016	JENSEN 14C-10-12-10	Salt Lake Meridian T12S R10E Sec 10: SWSW	BLUE TIP CASTLEGATE INC.	43-007-31453-0000	CARBON	UTAH
2080017	SHIMMIN TRUST 1-11-12-10	Salt Lake Meridian T12S R10E Sec 11: SWSW	BLUE TIP CASTLEGATE INC.	43-007-30673-0000	CARBON	UTAH
2080018	SHIMMIN TRUST 2-11-12-10	Salt Lake Meridian T12S R10E Sec 11: SESE	BLUE TIP CASTLEGATE INC.	43-007-30659-0000	CARBON	UTAH
2080019	SHIMMIN TRUST 4-14-12-10	Salt Lake Meridian T12S R10E Sec 14: SENW	BLUE TIP CASTLEGATE INC.	43-007-30662-0000	CARBON	UTAH
2080020	SHIMMIN TRUST 5-14-12-10	Salt Lake Meridian T12S R10E Sec 14: NWNE	BLUE TIP CASTLEGATE INC.	43-007-30122-0000	CARBON	UTAH
2080021	JENSEN 1-15-12-10	Salt Lake Meridian T12S R10E Sec 15: SWNE	BLUE TIP CASTLEGATE INC.	43-007-30736-0000	CARBON	UTAH
2080022	JENSEN DEEP 7-15-12-10	Salt Lake Meridian T12S R10E Sec 15: SWNE	BLUE TIP CASTLEGATE INC.	43-007-30786-0000	CARBON	UTAH
2080023	CASTLEGATE ST 1-16-12-10	Salt Lake Meridian T12S R10E Sec 16: NWNE	BLUE TIP CASTLEGATE INC.	43-007-30589-0000	CARBON	UTAH
2080024	CASTLEGATE ST 4-16-12-10	Salt Lake Meridian T12S R10E Sec 16: SENW	BLUE TIP CASTLEGATE INC.	43-007-30785-0000	CARBON	UTAH
2080025	JENSEN 1-18-12-10	Salt Lake Meridian T12S R10E Sec 18: NESE	BLUE TIP CASTLEGATE INC.	43-007-30718-0000	CARBON	UTAH
2080026	CASTLEGATE ST 1-35-12-10 WD	Salt Lake Meridian T11S R10E Sec 35: SWSW	BLUE TIP CASTLEGATE INC.	43-013-32308-0000	DUCHESNE	UTAH
2080027	CASTLEGATE ST 11-16H-12-10	Salt Lake Meridian T12S R10E Sec 16: NWNW	BLUE TIP CASTLEGATE INC.	43-007-30961-0000	CARBON	UTAH
2080028	JENSEN STATE 11C-34-11-9	Salt Lake Meridian T11S R9E Sec 34: NWNW	BLUE TIP CASTLEGATE INC.	43-049-30024-0000	UTAH	UTAH
2080030	JENSEN 41C-9-12-10	Salt Lake Meridian T12S R10E Sec 09: NENE	BLUE TIP CASTLEGATE INC.	43-007-31452-0000	CARBON	UTAH

29

ATTACHED LIST to Change of Operator Sundry Notice

BTC WELL NUMBER	WELL NAME AND NUMBER	LEGAL DESCRIPTION	OPERATOR	API	COUNTY	STATE
2080032	JENSEN 9-10-12-10	Salt Lake Meridian T12S R10E Sec 10: NESE	BLUE TIP CASTLEGATE INC.	43-007-30159-0000	CARBON	UTAH
2080033	SHIMMIN TRUST 11-11-12-10	Salt Lake Meridian T12S R10E Sec 11: NESW	BLUE TIP CASTLEGATE INC.	43-007-30166-0000	CARBON	UTAH
2080042	JENSEN 2C-9-12-10	Salt Lake Meridian T12S R10E Sec 9: NW4NE4	BLUE TIP CASTLEGATE INC.	43-007-01790-0000 50179	CARBON	UTAH
2080043	JENSEN FED 6-10-12-10	Salt Lake Meridian T12S R10E Sec 6: SE4NW4	BLUE TIP CASTLEGATE INC.	43-007-50177-0000	CARBON	UTAH

33

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

UIC FORM 5


TRANSFER OF AUTHORITY TO INJECT

Well Name and Number Castlegate St 1-35-12-10	API Number 4301332308
Location of Well Footage : 540' FSL, 1135' FWL County : Duchesne QQ, Section, Township, Range: SWSW 35 11S 10E State : UTAH	Field or Unit Name Castlegate Lease Designation and Number ML-48822

EFFECTIVE DATE OF TRANSFER: 7/1/2016


CURRENT OPERATOR

Company: Blue Tip Castlegate, Inc.  
Address: P. O. Box 842317  
city Houston state TX zip 77284  
Phone: (281) 944-3800  
Comments:


Name: Bruce L. Taylor  
Signature:   
Title: Secretary  
Date: 7/1/2016

NEW OPERATOR

Company: WEM Castlegate, LLC  
Address: 1411 East 840 North  
city Orem state UT zip 84097  
Phone:  
Comments:

Name: Cory Eusem  
Signature:   
Title: Manager  
Date: 7/11/16

(This space for State use only)

Transfer approved by:   
Title: UIC Geologist

Approval Date: 8/3/16

Comments:

RECEIVED

JUL 21 2016



Dustin K. Doucet  
Petroleum Engineer  
Division of Oil, Gas and Mining  
1594 West North Temple, Ste 1210  
Salt Lake City, Utah 84116

RE: Bonding for Castlegate Field Wells

August 15, 2016

Dustin:

Blue Tip Energy Management, LLC was the previous operator and bondholder of the Castle Gate Field and associated wells listed below. Liberty Pioneer Energy Source, Inc. ("LPES") has submitted the necessary paperwork to take over as the new operator of these wells. Per our recent communications we would like to make the following proposal pertaining to the bonding of the wells listed below so that all of the wells in the field will be covered by LPES blanket bond #RLB0012097.

1) LPES plans to P&A the following wells prior to November 1, 2016:

13318 CASTLEGATE ST 4-16-12-10  
14224 CASTLEGATE ST 11-16H-12-10

2) LPES is currently getting pricing to build a pipeline to the following well which is believed to be capable of production. If pricing is reasonable, LPES will propose production testing and flaring. We will notify you of our decision to either run a pipeline or plug and abandon this well before the end of 2016. If the decision is to produce, LPES will commence the pipeline permitting process before the end of 2016:

17071 JENSEN STATE 11C-34-11-9

3) Wells that are currently producing or will be returned to producing status by October 1, 2016:

13070 SHIMMIN TRUST 2-11-12-10  
13275 JENSEN 2-8-12-10  
13071 SHIMMIN TRUST 4-14-12-10  
13068 JENSEN 1-4-12-10  
18242 JENSEN 2C-9-12-10  
12991 CASTLEGATE FED 7-9-12-10  
11405 JENSEN 11-10-12-10  
12610 CASTLEGATE ST 1-16-12-10  
12611 JENSEN 1-10-12-10  
12903 JENSEN 1-9-12-10  
12904 JENSEN 16-9-12-10  
12905 JENSEN 5-10-12-10  
12906 JENSEN 9-10-12-10  
13072 JENSEN 1-15-12-10  
13247 JENSEN DEEP 7-15-12-10  
13317 JENSEN 2-9-12-10  
13359 JENSEN 1-8-12-10  
15766 JENSEN 42C-9-12-10  
15767 CASTLEGATE FED 22C-9-12-10  
15768 JENSEN 43C-9-12-10  
15769 JENSEN 33C-9-12-10  
15770 JENSEN 23C-9-12-10  
17235 JENSEN 14C-10-12-10  
17246 JENSEN 41C-9-12-10  
14226 JENSEN 1-18-12-10  
11410 SHIMMIN TRUST 11-11-12-10  
12901 SHIMMIN TRUST 1-11-12-10  
14175 SHIMMIN TRUST 5-14-12-10  
18209 JENSEN 6-10-12-10

Thanks for your help. Please let us know if you have any questions.

Sincerely,

A handwritten signature in black ink, appearing to read 'D. Gunnell', with a stylized flourish at the end.

Daniel R. Gunnell

President

Liberty Pioneer Energy Source, Inc.

1411 East 840 North

Orem, UT 84097



Rachel Medina &lt;rachelmedina@utah.gov&gt;

---

**Fwd: LPES plans for the Castlegate field wells/Bonding**2 messages

---

**Dayne Doucet** <daynedoucet@utah.gov>

Wed, Aug 17, 2016 at 11:46 AM

To: Rachel Medina &lt;rachelmedina@utah.gov&gt;, Randy Thackeray &lt;randythackeray@utah.gov&gt;

FYI

----- Forwarded message -----

From: **Daniel Gunnell** <dgunnell@rockiesstandard.com>

Date: Wed, Aug 17, 2016 at 9:40 AM

Subject: Re: LPES plans for the Castlegate field wells/Bonding

To: Dustin Doucet &lt;dustindoucet@utah.gov&gt;

Cc: Brad Gunnell &lt;bgunnell@rockiesstandard.com&gt;, Cory Jensen &lt;cjensen@rockiesstandard.com&gt;, Kimball Hodges &lt;khodges@rockiesstandard.com&gt;, Dayne Doucet &lt;daynedoucet@utah.gov&gt;, Joshua Payne &lt;joshuapayne@utah.gov&gt;

Dustin:

Thanks for your help with this! Please find Bond Proposal Letter attached.

If there is anything else you need please let me know. The Blue Tip guys are anxious to get their bond released.

Let me know if I need to send a hard copy of the letter.

Best,

Danny

On Mon, Aug 8, 2016 at 9:24 AM, Dustin Doucet &lt;dustindoucet@utah.gov&gt; wrote:

Danny,

Yes if you would just edit your previous plan and resubmit so there is no confusion. I think that would make it cleaner. If you decide to put a well online and have it online by the plugging deadline, then that should be fine.

Dustin

On Tue, Aug 2, 2016 at 4:31 PM, Daniel Gunnell &lt;dgunnell@rockiesstandard.com&gt; wrote:

Dustin:

Sorry for not getting back to you on this until now. There maybe a couple of wells that we may come back to you specifically on, but I think that we have now got a pretty good go forward plan that will meet and exceed your end of the year time frame for getting the wells in categories 2 and 3 in production.

There is one material change to my previous email that we want to make you aware of - instead of plugging the 11C-34 we are seriously considering running a pipeline to it and bringing online... not a final decision yet, but we are have got and are getting additional bids, and designing a test plan to better understand what production would look like.

Do I need to submit a formal letter with dates of Nov 1 for plugging and end of year to get wells on production under our existing bonds or are these emails sufficient?

Thanks for your help!

Best,

Danny



What time do you think you need? I would think by the end of the year max. If you can line out more justification, I'm open to listening to the reasoning.

Dustin

On Thu, Jun 30, 2016 at 12:21 PM, Daniel Gunnell <dgunnell@rockiesstandard.com> wrote:  
Dustin:

Sounds good. Thanks for your help.

Can we push back just a little to get as much time as possible for shut in wells that we need to come up with a plan for or plug (#2 in my original email?) - how much beyond Oct 2016 could you give us? We are going to be really busy so as much extra time as you can give really helps... we are reclaiming those evaporation ponds immediately, taking over operations, retrofitting the plant, plugging the identified wells, and ramping up production by reworking multiple shut-in wells that are we have already reviewed.

Let me know and thanks again.

Best,

Danny

On Thu, Jun 30, 2016 at 10:30 AM, Dustin Doucet <dustindoucet@utah.gov> wrote:  
Danny,

I would be o.k. with the timing and plan on part 1. The timing on part 2 does not work. Those have been SI/TA anywhere from 2.5 to 5 years. Did you mean October 2016? Our discussions were if you had a plan to produce or plug within a short period (meaning a few months), then we could forego increased bonding but increased bonding would be necessary if that wasn't accomplished. Part 3 would be similar to part 2 on the wells that have been SI/TA. The producing ones would probably be fine as you have 1 year allowed by rule (see below).

Production data through Jan 2016

13070	SHIMMIN TRUST 2-11-12-10 <u>SI since Sep 2014</u>
13275	JENSEN 2-8-12-10 <u>SI since Nov 2015</u>
13071	SHIMMIN TRUST 4-14-12-10 <u>SI since Dec 2015</u>
13068	JENSEN 1-4-12-10 <u>Produced 1 day in Jan 2016</u>
18242	JENSEN 2C-9-12-10 <u>Producing</u>
12991	CASTLEGATE FED 7-9-12-10 <u>Producing</u>
11405	JENSEN 11-10-12-10 <u>Producing</u>
12610	CASTLEGATE ST 1-16-12-10 <u>Producing</u>
12611	JENSEN 1-10-12-10 <u>Producing</u>
12903	JENSEN 1-9-12-10 <u>Producing</u>
12904	JENSEN 16-9-12-10 <u>Producing</u>
12905	JENSEN 5-10-12-10 <u>Producing</u>
12906	JENSEN 9-10-12-10 <u>Producing</u>
13072	JENSEN 1-15-12-10 <u>Produced 1 day in Jan 2016</u>
13247	JENSEN DEEP 7-15-12-10 <u>Produced 1 day in Jan 2016</u>

13359 JENSEN 1-8-12-10 Producing  
15766 JENSEN 42C-9-12-10 Producing  
15767 CASTLEGATE FED 22C-9-12-10 Producing  
15768 JENSEN 43C-9-12-10 Producing  
15769 JENSEN 33C-9-12-10 Producing  
15770 JENSEN 23C-9-12-10 SI since Nov 2015  
17235 JENSEN 14C-10-12-10 Producing  
17246 JENSEN 41C-9-12-10 Producing  
18209 JENSEN 6-10-12-10 Producing

On Fri, Jun 24, 2016 at 11:28 AM, Daniel Gunnell <dgunnell@rockiesstandard.com> wrote:

Dustin:

Per our recent conversation, I wanted to informally run our plans/bonding proposal for the Castle Gate Field by you for your comment prior to submitting a final proposal. Here is what we are considering:

Blue Tip Energy Management, LLC ("Blue Tip"), is the current operator and bondholder, of the Castle Gate Field and associated wells listed below ("Wells"). LPES should take over as the new operator effective July 1 2016. In anticipation of the transfer of operations and per our recent phone conversation we would like to make the following proposal pertaining to the LPES bonding of the wells listed below so that all of the wells in the field will be covered by LPES blanket bond #RLB0012097.

1) LPES will P&A the following wells prior to November 1, 2016:

17071 JENSEN STATE 11C-34-11-9  
14224 CASTLEGATE ST 11-16H-12-10

2) LPES will evaluate and propose a go forward plan after evaluation on the following shut-in wells prior to October 1 2017:

13318 CASTLEGATE ST 4-16-12-10  
14226 JENSEN 1-18-12-10  
11410 SHIMMIN TRUST 11-11-12-10  
12901 SHIMMIN TRUST 1-11-12-10  
14175 SHIMMIN TRUST 5-14-12-10

13070 SHIMMIN TRUST 2-11-12-10

13275 JENSEN 2-8-12-10

13071 SHIMMIN TRUST 4-14-12-10

13068 JENSEN 1-4-12-10

18242 JENSEN 2C-9-12-10

12991 CASTLEGATE FED 7-9-12-10

11405 JENSEN 11-10-12-10

12610 CASTLEGATE ST 1-16-12-10

12611 JENSEN 1-10-12-10

12903 JENSEN 1-9-12-10

12904 JENSEN 16-9-12-10

12905 JENSEN 5-10-12-10

12906 JENSEN 9-10-12-10

13072 JENSEN 1-15-12-10

13247 JENSEN DEEP 7-15-12-10

13317 JENSEN 2-9-12-10

13359 JENSEN 1-8-12-10

15766 JENSEN 42C-9-12-10

15767 CASTLEGATE FED 22C-9-12-10

15768 JENSEN 43C-9-12-10

15769 JENSEN 33C-9-12-10

15770 JENSEN 23C-9-12-10

17235 JENSEN 14C-10-12-10

17246 JENSEN 41C-9-12-10

18209 JENSEN 6-10-12-10

If this proposal is acceptable please let me know and I will submit a formal letter for approval. Thanks for your help.

Best,

Danny

-

Daniel R. Gunnell  
1411 East 840 North  
Orem, UT 84097  
(801) 224-4771

Confidentiality Notice--This electronic transmission and any attached documents or other writings are intended only for the person or entity to which it is addressed and may contain information that is privileged, confidential or otherwise protected from disclosure. Any disclosure, copying, distribution or the taking of any action concerning the contents of this communication or any attachments by anyone other than the named recipient is strictly prohibited. If you have received this communication in error, please consider the communication and any attachments as confidential and immediately notify sender by return e-mail and destroy the communication and any and all attachments.

-

Dustin K. Doucet  
Petroleum Engineer  
Division of Oil, Gas and Mining  
1594 West North Temple, Ste 1210  
Salt Lake City, Utah 84116  
801.538.5281 (ofc)  
801.359.3940 (fax)

web: [www.ogm.utah.gov](http://www.ogm.utah.gov)

-

Daniel R. Gunnell  
1411 East 840 North  
Orem, UT 84097  
(801) 224-4771

Confidentiality Notice--This electronic transmission and any attached documents or other writings are intended only for the person or entity to which it is addressed and may contain information that is privileged, confidential or otherwise protected from disclosure. Any disclosure, copying, distribution or the taking of any action concerning the contents of this communication or any attachments by anyone other than the named recipient is strictly prohibited. If you have received this communication in error, please consider the communication and any attachments as confidential and immediately notify sender by return e-mail and destroy the communication and any and all attachments.

-

Dustin K. Doucet  
Petroleum Engineer  
Division of Oil, Gas and Mining  
1594 West North Temple, Ste 1210  
Salt Lake City, Utah 84116  
801.538.5281 (ofc)  
801.359.3940 (fax)

web: [www.ogm.utah.gov](http://www.ogm.utah.gov)

--  
Daniel R. Gunnell  
1411 East 840 North  
Orem, UT 84097  
(801) 224-4771

Confidentiality Notice—This electronic transmission and any attached documents or other writings are intended only for the person or entity to which it is addressed and may contain information that is privileged, confidential or otherwise protected from disclosure. Any disclosure, copying, distribution or the taking of any action concerning the contents of this communication or any attachments by anyone other than the named recipient is strictly prohibited. If you have received this communication in error, please consider the communication and any attachments as confidential and immediately notify sender by return e-mail and destroy the communication and any and all attachments.

--  
Dustin K. Doucet  
Petroleum Engineer  
Division of Oil, Gas and Mining  
1594 West North Temple, Ste 1210  
Salt Lake City, Utah 84116  
801.538.5281 (ofc)  
801.359.3940 (fax)

web: [www.ogm.utah.gov](http://www.ogm.utah.gov)

--  
Daniel R. Gunnell  
1411 East 840 North  
Orem, UT 84097  
(801) 224-4771

Confidentiality Notice—This electronic transmission and any attached documents or other writings are intended only for the person or entity to which it is addressed and may contain information that is privileged, confidential or otherwise protected from disclosure. Any disclosure, copying, distribution or the taking of any action concerning the contents of this communication or any attachments by anyone other than the named recipient is strictly prohibited. If you have received this communication in error, please consider the communication and any attachments as confidential and immediately notify sender by return e-mail and destroy the communication and any and all attachments.

--  
Dayne Doucet  
Petroleum Engineer  
UDOGM  
801-538-5303

---

 **Statewide Bond Proposal.pdf**  
421K

---

**Dustin Doucet** <dustindoucet@utah.gov>

Wed, Aug 17, 2016 at 2:01 PM

To: Daniel Gunnell <dgunnell@rockiesstandard.com>, Rachel Medina <rachelmedina@utah.gov>

Cc: Brad Gunnell <bgunnell@rockiesstandard.com>, Cory Jensen <cjensen@rockiesstandard.com>, Kimball Hodges <khodges@rockiesstandard.com>, Dayne Doucet <daynedoucet@utah.gov>, Joshua Payne <joshuapayne@utah.gov>

Danny,

I think that looks fine. If the deadlines aren't met we will be looking for full cost bonding in addition to getting the wells back into compliance. I have copied Rachel Medina on this email so she can proceed with the operator change with this plan and conditions. thanks.